


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD



Stafford County. Sec. 26 Twp. 25 Rge. 13W (E) (W)
Location as "NE/CNW/SW" or footage from lines SW NW SE
Lease Owner Rock Island Oil & Refining Company
Lease Name Fisher Well No. 3
Office Address 321 West Douglas, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed November 9, 1964 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced October 29, 1964 19
Plugging completed November 9, 1964 19
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4300 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

255' of 8 5/8" surface pipe, cemented with 275 sacks. Fluid level in the hole was at 78', 1st cementing plug and 1/4 sack of hulls was pushed in fluid to 240', and cemented with 25 sacks, through the drill pipe. Fluid in the hole was now at a 38' level. 2nd cementing plug, bridged solid with hulls on fluid at 38', and cemented with 10 sacks to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

RECEIVED
STATE CORPORATION COMMISSION

JUN 20 1966

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Garvey Drilling Company
Address Route 2, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
T. D. Ables (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. D. Ables
321 W. Douglas, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 17th day of June, 1966

My commission expires December 8, 1969

Janice Lee
Janice Lee - Notary Public.


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 503 East Murdock, Wichita, Kansas

Company- ROCK ISLAND OIL & REFINING CO., INC.
 Farm- Fisher No. 3

SEC. 26 T. 25 R. 13W
 SW NW SE

Total Depth. 4300'
 Comm. 10-29-64 Comp. 11-9-64
 Shot or Treated.
 Contractor. Garvey Drlg. Co.
 Issued. 2-6-65

County Stafford
 KANSAS



Elevation. 1921 K B

Production. Dry

CASING:

8 5/8" 255' cem. w/275 sx.

Figures Indicate Bottom of Formations.

surface soil & sand	195
red bed	500
red bed & sand	775
Anhydrite	805
shale & shells	1700
lime & shale	1773
lime	2225
lime & shale	2360
shale & lime	2495
lime & shale	2650
shale & lime	3035
lime & shale	3210
lime	3550
shale & lime	3563
sand & shale	3663
lime	3839
Lime (Kansas City)	3889
lime	4088
shale	4105
lime (Mississippi)	4138
lime & chert	4200
chert & lime (Viola)	4233
shale & sand (Simpson)	4244
Simpson sand & shale	4270
shale & sand	4300
Rotary Total Depth	
TOPS	
Anhydrite	780
Heebner	3498
Toronto	3518
Douglas	3563
Brown Lime	3664
Lansing	3691
Base Kansas City	3962
Mississippi	4115
Viola	4149
Viola Chert	4166
Simpson	4240
Simpson Sand	4243

RECEIVED
 STATE CORPORATION COMMISSION

FEB 22 1966

CONSERVATION DIVISION
 Wichita, Kansas