

15-185-00818-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

Rev. 12/14/82
FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

API NUMBER N/A (6/20/55) (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR K & E Drilling, Inc. OPERATORS LICENSE NO. 5266

ADDRESS 100 S. Main, Suite 300, Wichita, KS, 67202 PHONE # (316) 264-4301

LEASE (FARM NAME) Leiss WELL NO. #1

WELL LOCATION NW SE NW SEC. 29 TWP. 25 RGE. 13 (X) or (W)

COUNTY Stafford TOTAL DEPTH 4339' FIELD NAME McCandless

check one:
OIL WELL X GAS WELL _____ INPUT WELL _____ SWD WELL _____ D&A _____

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? no, old well
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN A.S.A.P.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Orville Monroe ADDRESS 2008 11th St., Great Bend, KS, 67530

PHONE # (316) 792-2729

PLUGGING CONTRACTOR Kelso Casing Pulling LICENSE NO. 6050

ADDRESS Box 347, Chase, KS, 67524 PHONE # (316) 938-2457 RECEIVED
CORPORATION COMMISSION

INVOICE COVERING ASSESSMENT FOR PLUGGING THIS WELL SHOULD BE SENT TO: OCT 25 1984

NAME K & E Drilling, Inc. CONSERVATION DIVISION
Wichita, Kansas

ADDRESS 100 S. Main, Suite 300, Wichita, KS, 67202 PHONE # (316) 264-4301

AND PAYMENT WILL BE GUARANTEED BY APPLICANT OR ACTING AGENT.

SIGNED: Wayne L. Brinegar
(Applicant or Acting Agent)
Wayne L. Brinegar, President
DATE: October 24, 1984

(1)

State of Kansas



JOHN CARLIN
MICHAEL LENNEN
R. C. (PETE) LOUK
PHILLIP R. DICK
JUDITH MCCONNELL
BRIAN J. MDLINE

GOVERNOR
CHAIRMAN
COMMISSIONER
COMMISSIONER
EXECUTIVE SECRETARY
GENERAL COUNSEL

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1286

THIS NOTICE

JAN 29 1985

October 29, 1984

WELL PLUGGING NOTICE

EXPIRES

Leiss #1
NW SE NW
Sec. 29-25S-13W
Stafford County

K & E Drilling, Inc.
100 S. Main, Ste. 300
Wichita, KS 67202.

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

Jack M. McCord, Director

Please submit your proposal for plugging the above captioned well to
DIST. #1 302 West McArtor Dodge City, KS 67801

five days prior to plugging the well (KAR-82-3-113).

COMPLETION REPORT

McKnab Drilling Inc.-Leiss #1
NW SE NW Sec. 29-25S-13W
Stafford County, Kansas

6-23-55

Moved in Bill Hay Drilling Co. Cardwell Beam Rig #4, rigged up and swabbed hole down. String in to 4299.

6-24-55

Run Gamma Ray Log to correlate collars by Wellex. Perforated (4273 to 78-Schlumberger measurement) or 4269 to 74 Wellex measure. Finished Gamma Ray collar log at 9:25 A.M. Perforated at 9:52 A.M. w/ 20' Kleen Shot Jet Shots or 4 shots per ft. 10:00 A.M. Ran bailer after shooting. Recovered 5 gal. oil and 10 gal. drilling water. Ran bailer at 10:15 A.M. Recovered about same amount of oil and water as before. 10:25 A.M. Ran bailer and recovered same amount of oil and water as before. 10:40 A.M. Rigged up to swab. Swabbed as follows:
11:25 A.M.---5.85
12:25 P.M.---4.68
1:25 P.M.---4.68
2:25 P.M.---4.68
3:25 P.M.---4.68
4:25 P.M.---4.68
5:25 P.M.---4.68

Run bailer to deck bottom for mud. Hole clean. 6:07 P.M. Acidized with 500 gal. mud acid by Acid Engineers. Maximum pressure 200 lbs. Pressure drop to vacuum 1 min. 7:30 P.M. Started swabbing hole down. 11:30 P.M. Load back. Ran bailer. Hole clean.

6-25-55

Started swabbing as follows:
12:30 A.M.---11.11
1:30 A.M.---11.70
2:30 A.M.---11.70
3:30 A.M.---11.70
4:30 A.M.---11.11
5:30 A.M.---12.87
6:30 A.M.---12.87

Ran bailer, recovered about 3 gal. acid water off bottom. Hole clean. Strung up to run tubing and rods. RECEIVED STATE CORPORATION COMMISSION

Ben S. Lynch

BSL:m

OCT 25 1984

CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
JUL 5 1955
PETROLEUM MANAGEMENT, INC.