

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above Section Plat

Reno County, Sec. 30 Twp. 25 Rge. 4 (E) W (W)
 Location as "NE/CNW 1/4 SW 1/4" or footage from lines NE, SE, NW
 Lease Owner Bradley Bros et al
 Lease Name Soper Well No. 1
 Office Address 603 Petroleum Bldg., Wichita, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed Sept. 21, 19 50
 Application for plugging filed Sept. 21, 19 50
 Application for plugging approved Sept. 21, 19 50
 Plugging commenced Sept. 21, 19 50
 Plugging completed Sept. 21, 19 50
 Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
 Producing formation Depth to top Bottom Total Depth of Well 4126 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	199'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from top feet to bottom feet for each plug set.

Mud to 199ft, set plug and ~~XXXX~~
 dump 15 sacks cement; set plug at
 30 feet dump 10 sacks cement and
 complete

(If additional description is necessary, use BACK of this sheet)
 Correspondence regarding this well should be addressed to Beardmore Drilling Company
 Address 603 Petroleum Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
 (owner or operator) of the above-described well,
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
 (Signature) *[Signature]*
 603 Petroleum Bldg.
 (Address)

SUBSCRIBED AND SWORN to before me this 2ne day of October, 19 50

My commission expires October 11, 1952

28-8278-s 4-50-10M

PLUGGING
 FILE SEC-301 25 R 4w
 BOOK PAGE 30 LINE 24

RECEIVED
 STATE CORPORATION COMMISSION

OCT 2 - 1950
 CONSERVATION DIVISION
 Wichita, Kansas

10-2050

Super No. 1 Well

NE, SE, N W,
Section 30-25-17,
Reno County, Kansas

Drilled for: Bradley Bros et al
Drilled by: Beardmore Drilling Co.

Casing Record:

8-5/8" 199' w/150 sacks

Drilling Commenced: September 9, 1950
Drilling Completed: September 24, 1950

Elevation 1527 gr

<u>FORMATION</u>	<u>DEPTH</u>
Soil - clay	30
Shale - sand	100
Surface sand	199
Shale - shells	410
Shale	710
Lime broken	865
Lime - shale	1095
Shale - lime	1280
Lime	1310
Shale - shells	1825
Shale - lime	2055
Shale - shells	2230
Shale - lime	2575
Shale - shells	2690
Shale - lime	2825
Lime - shale	2940
Lime broken	3035
Lime broken	3090
Lime - shale	3190
Lime	3219
Sand	3239
Lime	3290
Lime - shale	3410
Lime	3457
Shale	3565
Lime	3610
Lime - chert	3690
Lime broken	3730
Lime	3814
Shale - shells	3855
Shale - lime	3925
Shale	3990
Lime	4005
Sand-Shale	4040
Simpson shale	4090
Lime (arbutle)	4126 T. D.

D & A

Top:

Lansing	2788
Mississippi Chat	3569
Kinderhook	3826
Viola	3986
Simpson	4003
Arbutle	4095

RECEIVED
STATE CORPORATION COMMISSION

OCT 2 - 1950

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS

COUNTY OF SEDGWICK

PLUGGING

FILE SEC 30-25-17
BOOK PAGE 30 LINE 74

I, the undersigned, being duly sworn on oath state that the above and within record and log is a true and correct statement regarding the well drilled on the location above-described to the best of my knowledge and belief.

[Signature]

Subscribed and sworn to before me this 2nd day of October, 1950.

My Commission Expires: Oct. 11, 1952.

[Signature]
Notary Public