


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Reno County. Sec. 18 Twp. 25S Rge. 4W K&W
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines

C- SW SE SW
Lease Owner Wildcat Oil & Gas Co., Inc.
Lease Name Emil Blocker Well No. 1
Office Address Box 1271, Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plat

Dry Hole
Date Well completed September 26, 1978
Application for plugging filed Verbal Application 19
Application for plugging approved Verbal Approval 19
Plugging commenced September 26, 1978
Plugging completed September 26, 1978
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation Depth to top Bottom Total Depth of Well 4,014'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	229'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy rotary mud from 4,014 ft. (rotary total depth) to 600 ft. Set plug at 600 ft. and cemented with 40 sacks cement. Filled hole with heavy rotary mud from 600 ft. to 240 ft. Set plug at 240 ft. and cemented with 40 sacks cement. Filled hole with heavy rotary mud from 240 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 12 sacks cement, 3 sacks cement in rat hole.

Plugging operations accomplished utilizing Sun Oilwell cementing pump truck through 4 1/2 inch drill pipe.


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oilwell Cementing, Inc.
Box 169, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Sedgwick, ss.
Dean Britting, Agent (Signature of owner) XXXXXXXXXXXXXXXXXXXX

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed, and that the same are true and correct. So help me God.

(Signature) Dean Britting
200 N. Main, Wichita, Kansas 67530
(Address)



Elsie Willison - Notary Public.

My commission expires July 25, 1982

RECEIVED
STATE CORPORATION COMMISSION

OCT - 2 1978
10-2-78
CONSERVATION DIVISION
Wichita, Kansas

KANSAS DRILLERS LOG

COMPANY Wildcat Oil & Gas Co., Inc.

SEC. 18 T. 25S R. 4W
LOC. C-SW SE SW

FARM Emil Blocker NO. 1

COUNTY Reno

ROTARY TOTAL DEPTH 4,014'
COMM. September 13, 1978 COMP. September 26, 1978
CONTRACTOR H-30, Inc.
ISSUED September 28, 1978

CASING

10 3/4"
8 5/8" Set at 229' cemented w/175 sxs cement
5 1/2"
4 1/2"

ELEVATION 1,520' K.B.

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand and Shale	232'
Shale and Shells	759'
Shale and Lime	1,281'
Lime and Shale	3,848'
Lime	3,916'
Lime and Shale	4,014'
Rotary Total Depth	4,014'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, Inc.

Dean Britting
Dean Britting

State of Kansas }
County of Sedgwick } SS:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 28th day of September, 1978.

Elsie Willison
Elsie Willison - Notary Public

My Commission Expires:

July 25, 1982

RECEIVED
STATE CORPORATION COMMISSION

OCT - 2 1978

CONSERVATION DIVISION
Wichita, Kansas

