

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Stafford SEC. 3 TWP. 25S RGE. 13W E/W
Location as in quarters or footage from lines.
330' W of NW SE SE SW

Lease Owner Brounger Oil, Inc.
Lease Name Copeland A Well No. #1
Office Address P.O. Drawer 1367 Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole):
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 11-5-81
Plugging completed 11-12-81
Reason for abandonment of well or producing formation Depleted

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J.H. Metz
Producing formation _____ Depth to top _____ bottom T.D. 4285'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	255'	none
				4-1/2"	4284'	3527'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Plugged off bottom with sand to 3825' and set 4 sacks cement. Shot casing @3515'
and pulled a total of 119 joints of pipe. Plugged well with 4 sacks hulls, 25 sacks
gel, 8-5/8" plug, 140 sacks 50/50 pos, 3% cc. Plugging Completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of November, 19 81

My Commission expires:



RECEIVED
STATE CORPORATION COMMISSION Notary Public.

NOV 20 1981 11-20-81

CONSERVATION DIVISION
Wichita, Kansas

WOODMAN & IANNITTI DRILLING COMPANY
Rotary Drilling Contractors
1008 DOUGLAS BUILDING
104 S. BROADWAY
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

OCT 9 1980

CONSERVATION DIVISION
Wichita, Kansas

December 22, 1980

Company; Brougner Oil, Inc.
Farm; #1 Copeland "A"
Location; 330' W of SE SE SW
Section; 3-25-13W
County; Stafford
Contractor; Woodman & Iannitti Drilling Co.
Comm; December 9, 1980
Completed December 17, 1980
Total Depth; 4285'
Casing; 8 5/8 @ 255' w/225 sx
Production; ~~8 5/8~~ @ 4284 w/150 sx.

4 1/2
Figures Indicate Bottom Of Formations;

255	Surface
787	Redbed
809	Anhy
1820	Shale
2625	Shale & lime
3345	Shale & lime
3718	Lime & shale
3835	Lime & shale
3920	Lime
4210	Lime & shale
4222	Lime & shale
4285	Lime

I certify the above to be a true and correct copy of the drillers log to the best of my knowledge and belief

Woodman & Iannitti Drilling Co.

K. T. Woodman
K. T. Woodman

Play at 4232
Perfs - 4197 to 4202
Perfs - 4186 to 4190
Perfs - 3883 to 3887