

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

RECEIVED

Form CP-4
Rev 12-15-80

WELL PLUGGING RECORD

HALLIBURTON OIL PRODUCING CO.

Give All Information Completely
Make Required Affidavit

COUNTY Stafford SEC. 10 TWP. 25S RGE. 13W E/W
Location as in quarters or footage from lines:

NW NE NW

Lease Owner Halliburton Oil Producing Company
 Lease Name Priess #1 Well No. _____
 Office Address Box 10 Stafford, Kansas 67578
 Character of Well (Completed as Oil, Gas or Dry Hole): _____
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced 11-5-81
 Plugging completed 11-9-81
 Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well J.H. Metz

Producing formation _____ Depth to top _____ bottom T.D. 4278'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	353'	none
				4-1/2"	4276'	3603'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

~~Plugged off bottom with sand 4174' and set 4 sacks cement. Shot casing @3811' and 3614'. Pulled a total of 109 joints of pipe. Plugged well with 25 sacks gel, 5 sacks hulls, 8-5/8" plug, 140 sacks 50/50 pos, 2% gel, 3% cc. Plugging Completed.~~

RECEIVED
STATE CORPORATION COMMISSION

DEC 10 1981

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Kelso Casing Pulling

CONSERVATION DIVISION
Wichita, Kansas

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelsp (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelsp
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of November, 1981

My Commission expires: 

Irene Hoover
Notary Public.