

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado De'by Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-22197-0000

LEASE NAME Fisher Farms

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 9 TWP. 25 RGE. 13 (Section) (W)

COUNTY Stafford

Date Well Completed

Plugging Commenced 11-21-95

Plugging Completed 11-22-95

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR KLM

ADDRESS 4 Olive Belpre, Ks. 67519

PHONE# (316) 995-3795 OPERATORS LICENSE NO. 308-52

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.O. 4401'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	272'	none
				5 1/2"	4325'	2745'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set plugged off bottom with sand to 4190' and 5 sacks cement. Shot pipe at 2745', pulled to 800', pumped 60 sacks cement; pulled to 300' pumped 40 sacks cement. Pulled out of hole, circulated to surface from 40' with 10 sacks cement. (60/40 pos 6% gel) Plugging complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 209 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: KLM Belpre, Ks. 67519

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Mike Kelso

(Address) P.O. Box 209 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 29th day of November, 19 95

Irene Herzberg
Notary Public

USE ONLY ONE SIDE OF EACH FORM



Form CP-4
Revised 05-88