


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plat

Stafford County, Sec. 8 Twp. 25S. Rge. (E) 13 (W)
Location as "NE/CNW/SE/SW" or footage from lines S/2 S/2 SW
Lease Owner Icer Addis
Lease Name O'Dell Well No. 1
Office Address 5307 East Central - Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 7, 1975
Application for plugging filed 1975
Application for plugging approved October 7, 1975
Plugging commenced October 7, 1975
Plugging completed October 7, 1975
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well George Russell Bieberstein
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4293 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface Casing	0	316			none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud from total depth to 250',
250 sacks cement plug, mud to 40'
10 sacks cement to ground level,
2 sacks in rathole, Job completed
at 10:00 A.M.

RECEIVED
STATE CORPORATION COMMISSION
OCT 20 1975
10-20-75
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Search Drilling Company
Address P. O. Box 18148 - Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick ss.
William J. Froelich, Jr. (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) William J. Froelich, Jr.
Wichita, Kansas (Address)

Subscribed and Sworn to before me this 15 day of October, 1975

My commission expires February 19, 1977
Maxine Dressen Notary Public.

MAXINE DRESSEN
NOTARY PUBLIC
SEDGWICK COUNTY, KANSAS
MY COMM. EXP. FEB. 19, 1977

DRILLERS LOG

O'DELL #1

<u>CASING RECORD:</u>	<u>OPERATOR:</u> Icer Addis	<u>DESCRIPTION</u>
	<u>CONTRACTOR:</u> Search Drilling Company	S/2 S/2 SW Section 8--25S-13W Stafford County, Kansas
<u>TOTAL DEPTH:</u>	<u>COMMENCED:</u> September 28, 1975	
	<u>COMPLETED:</u> October 7, 1975	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand and Redbed	0	329	
Shale	329	725	
Sand and Clay	725	800	
Anhydrite	800	814	
Sand, Clay and Shale	814	1695	
Shale, Lime	1695	1927	
Shale and Lime	1927	2240	
Lime and Shale	2240	2495	
Lime and Shale	2495	2730	
Lime and Shale	2730	2941	
Lime and Shale	2941	3136	
Lime and Shale	3136	3440	
Lime and Shale	3440	3582	
Lime and Shale	3582	3651	
Brown Lime	3651	3665	
Lime	3665	3720	
Lime	3720	3736	
Chert and Lime	3736	3754	
Lime and Chert	3754	3825	
Lime	3825	3880	
Lime	3880	3958	
Lime and Shert	3958	4045	
Lime, Chert and Shale	4045	4122	
Chert (Viola)	4122	4200	
Chert, Sahle and Sand	4200	4250	
Simpson	4250	4252	
Arbuckle	4252	4291	
Total Depth		4293	Dry and Abandoned

RECEIVED
STATE CORPORATION COMMISSION

OCT 20 1975

CONSERVATION DIVISION
Wichita, Kansas

(Faint mirrored text from reverse side of page)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SEARCH DRILLING COMPANY

(Signature)
William J. Froelich, Jr.

Subscribed and sworn to before me this 15th day of October, 1975

My commission expires:
February 19, 1977

(Signature)
Maxine Dressen
Notary Public

MAXINE DRESSEN
NOTARY PUBLIC
SEDGWICK COUNTY, KANSAS
MY COMM. EXP. FEB. 19, 1977