

TYPE OR PRINT  
 NOTICE: Fill out completely and return  
 to Cons. Div. office within 30 days.

       Ft. from S/N Line of Section (circle one)

       Ft. from E/W Line of Section (circle one)

LEASE OPERATOR Sabre Petroleum

SPOT LOCATION C5 1/2 SW SE

ADDRESS Route 1

SEC. 7 TWP. 25S S. RGE 13 (E) or (W)

CITY, STATE, ZIP Preston, Kansas 67569

COUNTY STAFFORD

PHONE# (316) 656-4761 OPERATORS LICENSE NO. 4385

Date Well Completed       

Character of Well Oil  
 Oil  Gas, D&A, SWD, Input, Water Supply Well)

Date Plugging Commenced 1-19-99

Date Plugging Completed 2-4-99

The plugging proposal was approved on January 19, 1999 (date)

by Steve Pfeifer (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached?       

Producing Formation(s) 4066' - 4072' (Perforations) Depth to Top        Bottom 4340 T.D. 4450'

Show depth and thickness of all water, oil and gas formations. 1959 KB

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
	Surface Casing	0'	290'	8 5/8"	290'	0
	Prod. Casing	0	4340'	5 1/2"	4340'	1797'

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from        feet to        feet each set.

(1-19-99) Sanded back to 3960', Dumped 10 sxs Cement, Found Free point and Shot Casing off at 1797 Ft., Pulled 56 joints of 5 1/2" Casing. (2-2-99) Allied Cement pumped 300 #5 Hulls, 10 sxs Gel, 50 sxs Cement, 10 sxs Gel, 100 #5 Hulls, 100 sxs Cement.  
(2-4-99) Tagged Top of Cement at 75' down, Dumped 4 BBLs. Sand and capped off w/ 2 sxs Cement.  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pratt Well Service Inc.

License No. 5893

Address P.O. Box 847 Pratt, Ks. 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Sabre Petroleum

STATE OF Kansas COUNTY OF Stafford, ss.

Stephen E. Hart, C/O Pratt Well Service Inc. (Employee of Operator or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Stephen E. Hart

(Address) P.O. Box 847, Pratt, Ks 67124

SUBSCRIBED AND SWORN TO before me this 19<sup>th</sup> day of February, 19 99

Kenneth W. Ferguson  
 Notary Public

My Commission Expires: 06/19/00



RECEIVED  
 KANSAS CORP. COMM.  
 1999 FEB 22  
 2-22-99