

API NUMBER 15-185-00822-0000
 LEASE NAME ODELL
 WELL NUMBER ONE
330' Ft. from (S)N Line of Section (circle one)
990' Ft. from (E)W Line of Section (circle one)

TYPE OR PRINT
 NOTICE: Fill out completely and return
 to Cons. Div. office within 30 days.

LEASE OPERATOR Sabre Petroleum
 ADDRESS Route #1
 CITY, STATE, ZIP Preston, Kansas 67569
 PHONE#() _____ OPERATORS LICENSE NO. 4385
 Character of Well Oil
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

SPOT LOCATION SW - SE - SE
 SEC. 7 TWP. 25 S. RGE 13 (E) or (W)
 COUNTY Stafford
 Date Well Completed _____
 Date Plugging Commenced 1-26-99
 Date Plugging Completed 2-4-99

The plugging proposal was approved on January 19, 1999 (date)
 by Steve Pfeifer (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached? _____
 Producing Formation(s) 4294'-4304', 3889'-3899' Depth to Top _____ Bottom _____ T.D. 4308
 Show depth and thickness of all water, oil and gas formations. PBTD 3955 1962 KB

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
	Surface Casing	0'	252'	8 5/8"	252'	0'
	Production Casing	0'	4307'	5 1/2"	4307'	1936'

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
1-26-1999 Tagged at 3849', Dumped 1 3/4 BBL Sand - Let settle for 2hrs., Tagged at 3736'
Dumped 5 Sxs Cement, (1-27-1999) Found Free point - Shot Casing off at 1936', Pulled & Laid down 49jts of 5 1/2" Casing plus 4' Sub. (2-2-1999) Allied cement pumped 300 #s Hulls, 10sxs Gels, 50 Sxs Cement, 10 Sxs Gel, 100 #s Hulls, 100sxs Cement (2-4-1999) Tagged 95' down, Sand Back 5 BBLs, Capped top w 2sxs Cement
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pratt Well Service Inc.
 License No. 5893
 Address P.O. Box 847 Pratt, Ks. 67124
 NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Sabre Petroleum
 STATE OF Kansas COUNTY OF Stafford, ss.

Stephen E. Hart c/o Pratt Well Service Inc. (Employee of Operator or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Stephen E. Hart
 (Address) P.O. Box 847, Pratt Ks. 67124

SUBSCRIBED AND SWORN TO before me this 19th day of February, 1999
Kenneth W. Ferguson
 Notary Public

My Commission Expires: 06/19/00

KENNETH W. FERGUSON
 Notary Public - State of Kansas
 My Appt. Expires 06/19/00

RECEIVED
 KANSAS CORP. COM.
 1999 FEB 22
 2-22-99
 39