

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

	7		
0			

Locate well correctly on above
Section Plat

Stafford County, Sec. 7 Twp. 25S Rge. 13 (E) (W)
 Location as "NE/CNWxSWx" or footage from lines. NW NE SW
 Lease Owner: Petroleum, Inc.
 Lease Name: Kachelman Well No. 1
 Office Address: 305 East Third, Wichita 2, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole): Dry Hole
 Date well completed: December 31, 1952
 Application for plugging filed: December 31, 1952
 Application for plugging approved: December 31, 1952
 Plugging commenced: December 31, 1952
 Plugging completed: December 31, 1952
 Reason for abandonment of well or producing formation: Dry Hole

If a producing well is abandoned, date of last production: 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well: Mr. M. A. Rives
 Producing formation: Depth to top: Bottom: Total Depth of Well: 4343 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	280'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up to and set wooden plug at 270',
 preceded by 1/4 sack of hulls wrapped in sack.
 Cemented and displaced 20 sacks cement through
 drill pipe onto plug at 270'. Mudded up to
 35' and set second wooden plug, preceded by
 1/4 sack hulls wrapped in sack. Filled hole to
 bottom of well cellar with 10 sacks cement.

RECEIVED
 JAN 9 1953
 CONSERVATION COMMISSION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor: Garvey Drilling Company
 Address: R. R. #2, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
 W. W. Fisher (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. W. Fisher
 305 East Third, Wichita 2, Kansas
 (Address)

SUBSCRIBED AND SWORN TO before me this 6th day of January, 1953

Sharonne Sheidman
 Notary Public.

My commission expires October 13, 1954

PLUGGING
 FILE SEC 7 T 25 R 13
 BOOK PAGE 20 LINE 4

DRILLERS LOG KACHELMAN NO. 1

Petroleum, Inc., Operator
Garvey Drilling Company, Contractor
Drilling Commenced: December 14, 1952
Drilling Completed: December 31, 1952
Casing Record: 8 5/8" @ 280' w/225 sax

Section 7, Twp. 25S, Rge. 13W
Location: NW NE SW
County: Stafford County, Kansas
R.T.D.: 4343
Production: D & A

Figures below indicate bottom of formation:

165 Sand
240 Shale
280 Red Bed
800 Red Bed, Shale & Shells
825 Shale & Shells
855 Anhydrite
1765 Shale & Shells
2330 Lime
3355 Shale & Lime
3428 Lime
3535 Lime & Shale
4041 Lime
4117 Chert & Lime
4189 Lime
4270 Lime & Chert
4310 Lime
4318 Simpson
4343 Lime
4343' R.T.D.

Tops:

Heebner: 3527 (-1563)
Brown Lime: 3669 (-1705)
Lansing: 3686 (-1722)
Miss.-Cg.: 4045 (-2081)
Kinderhook: 4095 (-2131)
Viola: 4157 (-2193)
Arbuckle: 4318 (-2354)

DST #1, 4058-81, open 1 hr., rec. 120' gas, 45' slightly gas cut mud, 70#BHP
DST #2, 4172-4236, open 1 hr., rec. 250' muddy water, 1450# BHP.

I hereby certify that this is a true and correct log of the above mentioned well.

PETROLEUM, INC.

RECEIVED
CORPORATION COMMISSION

By W.W. Fisher

STATE OF KANSAS)
COUNTY OF SEDGWICK)

SS: JAN 8 - 1953
CONSERVATION DIVISION
Wichita, Kansas

Subscribed to and sworn to before me, a Notary Public, in said County and State, this 6th day of January, 1953.

PLUGGING
FILE SEC 7 1 25 R 133
BOOK PAGE 70 LINE 4

Charlotte Haisman
Notary Public

My commission expires: October 13, 1954.