


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Stafford County. Sec. 13 Twp. 25S Rge. 13WE/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
Continental Oil Co. 590' FNL + 1150' FEL  
Lease Owner Continental Oil Co.  
Lease Name SouthLeesburg Well No. 205  
Office Address Box 267 Great Bend Kansas  
Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_



Locate well correctly on above.  
Section Plot

Oil  
Date Well completed 9/16 19 64  
Application for plugging filed 12/5 19 76  
Application for plugging approved \_\_\_\_\_ 19 76  
Plugging commenced 1/31 19 77  
Plugging completed 2/15 19 77  
Reason for abandonment of well or producing formation \_\_\_\_\_

Dry  
If a producing well is abandoned, date of last production \_\_\_\_\_  
1/31 1976  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bud Metz  
Producing formation arb. Depth to top 4129 Bottom 4131 Total Depth of Well 4131  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	319	8 5/8		
		0	4130	5 1/5		2430

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sand to 3580 Dumped 4 sx. Cement

Pumped top with 3 sx. hulls 20 sx. jell and 100 sx. cement 4 % jell

RECEIVED

STATE CORPORATION COMMISSION

MAR 10 1977


3-16-77

Conservation Division  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Nicholas Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.  
(employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George B. Nicholas  
(Address) \_\_\_\_\_



before me this 11th day of March, 1977  
Glenn M. Stegman  
Glenn M. Stegman Notary Public.

My commission expires 7/6/77

to the "class"  
rd 2 minutes

DRILLERS LOG

Loesbury South Unit No. 205  
No. 5 Maggie Russell

CASING RECORD:	COMPANY:	Continental Oil Co.	DESCRIPTION:
8 5/8" @ 321' w/150 sx cement	CONTRACTOR:	Red Tiger Drilling Co.	570' from North Line 1150' from East Line 13-258-13W Stafford Co., Kansas
5 1/2" @ 4130' w/200 sx cement	COMMENCED:	August 22, 1964	ELEVATION:
	COMPLETED:	September 4, 1964	
TOTAL DEPTH: 4131'			

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand	0	135	
Shale, Lime & Shells	135	322	
Red Bed & Sand	322	727	
Anhydrite	727	740	
Shale & Shells	740	1470	
Shale	1470	1830	
Lime & Shale	1830	2700	
Shale	2700	2985	
Lime & Shale	2985	3240	
Lime	3240	3955	
Lime & Chert	3955	4091	
Shale	4091	4131	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

George A. Angle  
George A. Angle

Subscribed and sworn to before me this 9th day of September, 1964.

Dennis B. Head  
Notary Public

My Commission Expires:

11-17-66

RECEIVED  
JAN 21 1977  
COMM. EXPIRES 11-17-66