

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Stafford

County. Sec. 14 Twp. 25S Rge. 13 (W)

Location as "NE/CNW/SW" or footage from lines W $\frac{1}{2}$ SW NW

Lease Owner Rains & Williamson Oil Co., Inc.

Lease Name HARRY RUSSELL Well No. 1

Office Address 1425 Wichita Plaza - Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 2-26 19 67

Application for plugging filed 2-26 19 67

Application for plugging approved 2-26 19 67

Plugging commenced 2-26 19 67

Plugging completed 2-26 19 67

Reason for abandonment of well or producing formation No oil or gas found
in commercial quantities.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving, Pratt, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4291 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	309.30	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pushed hulls and plug to 260' and cemented through drill pipe with 25 sacks. Mud back to 40', set solid bridge and capped with 10 sacks; 2 sacks in rat hole.
Plugging completed at 3:15 P.M., 2-26-67

RECEIVED
STATE CORPORATION COMMISSION
MAR 1 1967

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Rains & Williamson Oil Co., Inc.
Address 1425 Wichita Plaza Bldg. - Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Wilson Rains

(Signature) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains

1425 Wichita Plaza - Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 28 day of February, 1967

My commission expires March 3, 1970

Mary J. Brown
Notary Public.

ROTARY DRILLING LOG

Operator: Rains & Williamson Oil
Co., Inc.
#1 HARRY RUSSELL
W $\frac{1}{2}$ SW NW Section 14-25S-13W
Stafford County, Kansas

Contractor: Rains & Williamson
Oil Co., Inc.
Commenced: 2-15-67
Completed: 2-26-67

Remarks: Set 8-5/8" surface
casing at 309.30'
with 250 sacks GL-3

Formations:

Sand	180'
Shale and Red Beds	220'
Red Beds	309'
Shale and Sand	470'
Shale and Red Beds	775'
Anhydrite	805'
Shale and Shells	1680'
Lime and Shale	1851'
Lime	2005'
Lime and Shale	2240'
Shale and Lime	2445'
Lime and Shale	2920'
Shale and Lime	3100'
Shale	3215'
Lime	3455'
Lime and Shale	3735'
Lime	4018'
Lime and Shert	4191'
Lime	4240'
Sand	4270'
Lime	4291'
ROTARY TOTAL DEPTH (D & A)	4291'

RECEIVED
STATE CORPORATION COMMISSION

MAR 1 1967

CONSERVATION DIVISION
Wichita, Kansas

We certify the above log is
true and correct to the best of
our knowledge and belief.

RAINS & WILLIAMSON OIL CO., INC.

Wilson Rains
Wilson Rains

Subscribed and sworn to before me, a Notary Public in and for the State of
Kansas, County of Sedgwick, this 28 th day of February, 1967.

Mary J. Brown
Mary J. Brown Notary Public

My Commission Expires: March 3, 1970