

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

WELL PLUGGING RECORD

Reno County, Sec. 2 Twp. 25 Rge. 8W (E) (W)

Location as "NE/CNW/SW" or footage from lines NW NW NE

Lease Owner Tomlinson-Kathol, Inc. & Shawver-Armour

Lease Name Linscheid Well No. 1

Office Address 414 Union Center, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 7/16 19 59

Application for plugging filed 7/16 19 59

Application for plugging approved 19

Plugging commenced 7/16 19 59

Plugging completed 7/16 19 59

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel

Producing formation Depth to top Bottom Total Depth of Well 4250 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface casing set at 242 cemented with 200 sacks					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

18 sacks @ 240

10 Sacks @ 40

RECEIVED  
STATE CORPORATION COMMISSION

JUL 24 1959

RECEIVED  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION  
Wichita, Kansas

JUL 28 1959

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Tomlinson-Kathol, Inc.

Address 414 Union Center, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Gerald J. Kathol (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gerald J. Kathol

414 Union Center (Address)

SUBSCRIBED AND SWORN TO before me this 20th day of July, 19 59

Ester Lanson Notary Public.

My commission expires Jan. 19, 1961

PLUGGING  
FILE SEC 2 T. 25 R. 8W  
BOOK PAGE 52 LINE 01

DRILLER'S LOG  
 TOMLINSON-KATHOL, INC.  
 & SHAWVER-ARMOUR, ETAL  
 # 1 LINSCHIED  
 NW NW NE, SEC. 2-25S-8W  
 RENO COUNTY, KANSAS


Contractor - Tomlinson-Kathol, Inc.

Commenced: 7/1/59  
 Completed: 7/16/59  
 Elevation: 1613 KB

From	To	Description	Remarks
0	112	Sand & Gravel	
112	220	Clay	
220	242	Blue Shale	245' 8-5/8" Surf. Csg.
242	1210	Shale	w/200 Sks cement
1210	1260	Anhydrite	
1260	1325	Shale & Lime	
1325	1390	Lime & Salt	
1390	1751	Shale & Lime	
1751	1975	Shale	
1975	2195	Shale & Lime	2195
2195	2350	Shale	
2350	2540	Shale & Lime	
2540	2705	Shale	
2705	2816	Lime & Shale	
2816	3223	Shale & Lime	
3223	3713	Lime	
3713	3762	Shale	
3762	3776	Lime - Shale	
3776	3800	Lime	
3800	3879	Chert	
3879	3911	Lime	
3911	4114	Shale	Heebner 3304
4114	4140	Shale & Lime	Toronto 3058
4140	4177	Lime - Shale	Douglas Sd 3080
4177	4200	Shale	Brown Lime 3192
4250		Rotary Total Depth	Lansing 3210
			Miss Chat 3784
			Kinderhook 3894
			Viola 4132
			Simpson 4152
			Arbuckle 4224

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 JUL 24 1959  
 CONSERVATION DIVISION  
 Wichita, Kansas

I certify to the best of my knowledge and belief, the above represents a true and accurate Driller's Log record of the captioned well.

  
 Gerald J. Kathol

State of Kansas )  
 )  
 County of Sedgwick )

Subscribed and sworn to before me this 21st day of July, 1959.

  
 Notary Public

My Commission expires Jan. 19, 1961

PLUGGING  
 FILE SEC. 2 T. 25 R. 8W  
 BOOK PAGE 52 LINE 21