

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Reno County, Sec. 22 Twp. 25S Rge. 8 (E) W

Location as "NE/CNW/SE/SW" or footage from lines _____
Lease Owner Pickrell Drilling Company
Lease Name Sutton "A" Well No. 1
Office Address 705 Fourth Nat'l. Bk. Bldg.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 14, 1974 19 74
Application for plugging filed June 14, 19 74
Application for plugging approved June 14, 19 74
Plugging commenced June 14, 19 74
Plugging completed June 14, 19 74
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4159 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	226'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud from RTD to 400'
40 sacks cement at 400'.
Heavy mud to 200'
20 sacks cement at 200'.
Heavy mud to 40'
10 sacks cement bridged at 40'.
Job completed 4:45 P.M. 6/14/74

RECEIVED
STATE CORPORATION COMMISSION
6-28-74
JUN 28 1974

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pickrell Drilling Company
Address 705 Fourth Nat'l. Bk. Bldg. Wichita, KS 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. W. Sebitts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts
705 Fourth Nat'l. Bk. Bldg. Wichita, KS 67202
(Address)

SUBSCRIBED AND SWORN to before me this 24th day of June, 19 74

My commission expires August 19, 1975

Helen L. Martin
Helen L. Martin

Notary Public.

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
705 Fourth Nat'l. Bk. Bldg.
Wichita, Kansas 67202
LOCATION: Sitton "A" #1.
C SE SE Sec. 22 25S 8W
Reno County, Kansas
CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

Rotary Drilling Commenced 6/4/74
Rotary Drilling Completed 6/14/74

CASING RECORD: (6 joints) 8 5/8 surface casing set at 226 and cemented with 165 sacks cement. Job completed 6-6-74. D & A., plugged 6-14-74

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

730	Red Rock-shale	
1370	Shale & Lime	
1540	Lime	C. F. S.
1865	Lime & Shale	1450'
2035	Shale	2245'
2538	Lime & Shale & Sand	2515'
3099	Shale & Lime	3055'
3245	Sand	3115'
3325	Lime & Shale	3285'
3490	Lime	3460'
3570	Lime & Shale	3522'
3745	Lime	3732'
3860	Lime & Chert	3786'
3874	Chert	3790'
3975	Lime	4140'
4060	Lime & Shale	4150'
4134	Shale	4159'
4159 RTD	Lime	

RECEIVED
STATE CORPORATION COMMISSION

JUN 28 1974

CONSERVATION DIVISION
Wichita, Kansas

Slope Tests
3000'
3500'
4000'

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 27th day of June, 1974, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: August 19, 1975

Helen L. Martin
Helen L. Martin Notary Public