


STATE OF KANSAS  
STATE CORPORATION COMMISSION

## WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202



Locate well correctly on above  
Section Plat

Reno County. Sec. 10 Twp. 25 Rge. 6 E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
C SE SE

Lease Owner F & M Oil Co., Inc.  
Lease Name Smyth Well No. 1  
Office Address 603 Union Center Bldg, Wichita, Ks. 67202  
Character of Well (Completed as Oil, Gas or Dry Hole)

Dry Hole

Date Well completed August 14 19 76  
Application for plugging filed August 14 19 76  
Application for plugging approved August 14 19 76  
Plugging commenced August 14 19 76  
Plugging completed August 14 19 76  
Reason for abandonment of well or producing formation  
Dry Hole

If a producing well is abandoned, date of last production  
19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman  
Producing formation Depth to top Bottom Total Depth of Well 4059  
Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

## CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole full of heavy mud to 500' with 40 sacks cement thru drill pipe.  
Mud to 250' w/25 sacks cement thru drill pipe.  
Mud to 40' w/ $\frac{1}{2}$  sack hulls plug and 10 sacks cement.  
2 sacks cement in rat hole.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 19 1976  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co.

STATE OF KANSAS COUNTY OF BARTON, ss.  
Larry Curtis (employee of owner) or (~~owner~~)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Box 823, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of August, 19 76

*Dorothy M. Hague*  
Notary Public.

My commission expires April 11, 1978

# DRILLERS' WELL LOG

DATE COMMENCED: August 4, 1976  
DATE COMPLETED: August 14, 1976

F & M Oil Company  
SMITH # 1  
C SE SE  
Sec 10-T25-R6W  
Reno County, Kansas

ELEVATION: 1518 K.B.

0 - 257'	Sand, Hard Sand, Red Bed
257 - 793'	Shale
793 - 2160'	Shale and Lime
2160 - 2275'	Lime and Shale
2275 - 2634'	Lime
2634 - 2638'	Shale
2638 - 2894'	Lime and Shale
2894 - 3545'	Lime
3545 - 3977'	Chert and Lime
3977 - 4013'	Chert
4013 - 4059'	Sand
4059'	RTD

## FORMATION TOPS

Howard	2160
Topoka	2275
Hesbner	2634
Drown Lime	2861
Lansing K.O.	2894
Mississippi	3545
Viola	3977
Simpson Sand	4013
RTD	4059

SURFACE PIPE:  
Set used 8 5/8", 23# pipe  
@ 257' w/200 sacks Common,  
2 1/2 Gal, 3 1/2 cc.

## AFFIDAVIT

STATE OF KANSAS } ss.  
COUNTY OF BARTON }

Larry Curtis, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Larry Curtis

Subscribed and sworn to before me this 17th day of August, 1976.

Marion M. Hague  
Notary Public

My Commission Expires: April 11, 1978