

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittig Building
Wichita, Kansas

Reno County. Sec. 22 Twp. 25 Rge. (E) 6 (W)

Location as "NE/CNW/SW" or footage from lines SW SE SE

Lease Owner Petroleum, Inc.

Lease Name BTNFORD Well No. 1

Office Address 311 East Third, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed October 3 19 55

Application for plugging filed October 3 19 55

Application for plugging approved October 3 19 55

Plugging commenced October 3 19 55

Plugging completed October 3 19 55

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Ruel Durkee, McPherson, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 1090 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	232'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded up to 220' and set wooden plug at 220'.

Placed 1/2 sack hulls on top of plug and displaced

15 sacks cement through drill pipe onto hulls.

Mudded up to 25' and set second wooden plug and

placed 1/2 sack of hulls on top of plug. Filled

hole to base of well cellar with 5 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company

Address R. R. #2 - Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Karl E. Becker (employee of owner) or (~~owner or operator~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Karl E. Becker

311 East Third, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 3rd day of October, 19 55

My commission expires September 2, 1959

Frances Sloan
Notary Public.

Frances Sloan, Notary Public
My commission expires Sept. 2, 1959

PLUGGING
FILE SEC 22 T 25 R 6 W
BOOK PAGE 6 LINE 12

10-14-55
DIVISION
Wichita, Kansas

WELL LOG

COMPANY **Petroleum, Inc.**

SEC. **22** T. **25S** R. **6E**

FARM **BINFORD**

NO. **1**

LOC. **SW SE SE**
990' TEL
330' TEL
COUNTY **Reed**


TOTAL DEPTH **4090'**

COMM. **September 19, 1955**

COMP. **October 3, 1955**

CONTRACTOR **Garvey Drilling Company**

CASING **8-5/8" @ 231 w/125 case**



ELEVATION **2150' OF**
2150' BS

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

290	Shale & Red Bed
645	Shale & Shells
655	Anhydrite
670	Shale & Shells
1220	Shale & Lime
1250	Salt & Shale
2300	Shale & Lime
2930	Lime
2997	Shale & Lime
3131	Lime
3197	Lime & Shale
3350	Lime
3512	Lime & Shale
3520	Conglomerate
3706	Mississippi
3850	Lime & Shale
3892	Lime, Shale & Sand
3898	Sand & Shale
3920	Lime & Shale
3935	Lime
3949	Sand
4053	Lime & Shale
4090	Arbuckle

Sample Tops

Heckman	2577	(-1121)
Douglas	2530	(-1174)
Brown Lime	2313	(-1357)
Lansing	2313	(-1357)
Conglomerate	3523	(-2057)
Miss. Chert	3510	(-2084)
Miss. Lime	3500	(-2124)
Miss. Dolomite	3652	(-2196)
Kinderhook	3723	(-2267)
Viola	3931	(-2475)
Arbuckle	4052	(-2596)

RED 4090'

State of **KANSAS**

County of **SEDGWICK**

I, **Karl E. Becker**

of **Petroleum, Inc.**

upon oath state that the above and foregoing is a true and correct copy of the log of the **BINFORD #1** well

Subscribed and sworn to before me this **12th** day of **October** 19**55**

My Commission Expires: **September 2, 1959**

Karl E. Becker

Francis Sloan
Notary Public
My Commission expires 9-2-59

RECEIVED
STATE COMMISSION

OCT 14 1955

PLUGGING
FILE SEC. 22 T. 25 R. 6E
BOOK PAGE 4 LINE 12