


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Reno County. Sec. 28 Twp. 25 Rge. 6 W (E) (W)
Location as "NE/CNW/SW" or footage from lines SW NW NW
Lease Owner V. E. Wiggins
Lease Name Goering Well No. I
Office Address Box 191 McPherson, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed _____ 19____
Application for plugging filed August 19 65
Application for plugging approved August 19 65
Plugging commenced Aug 11 19 65
Plugging completed Aug 14 19 65
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4,024' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				7"		2,876'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pushed plug to 3,610'. Made 10' of sand. Dumped 6 sx of cement at 3,600'. Mudded hole to 300'. Made 10' of rock bridge. Dumped 25 sx of cement. Mudded hole to 25'. Made 5' of rock bridge. Dumped 10 sx of cement, filling to the bottom of the cellar.

RECEIVED
STATE CORPORATION COMMISSION
AUG 18 1965
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Art Lamb Casing Pulling Co.
Address 2809 King St. Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Reno, ss.
Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
2809 King St. Hutchinson, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 14 th day of August, 19 65

My commission expires January 5, 1966
[Signature] Notary Public!

GLICKMAN OIL COMPANY

P. O. Box 3108
Wichita, Kansas

DRILLERS WELL LOG

Company: **Vaughn E. Wiggins**

Location: **SW NW NW
Sec. 28-25S-6W
Reno County, Kansas**

Farm: **Goering** Well No. **1**

Commenced: **June 10, 1960**
Completed: **June 27, 1960**
Total Depth: **3987 R. TD**

Elevation: **1550 Ground Level**

Casing: **300' 10-3/4" Surface Casing
3985.50 - 7" Casing**

Production:

Figures Indicate Bottom of Formations

300	Shale & Shells
480	Shale & Lime Shells
750	Shale
1035	Shale & Lime
1155	Lime & Shale
1375	Lime
1675	Lime & Shale
1955	Shale & Lime
2155	<u>Lime & Shale</u>
2800	Lime & Shale
2908	Sand & Shale
2920	Shale & Lime
3000	Lime & Shale
3370	Lime
3484	Lime & Shale
3572	Shale w/lime streaks
3617	Shale & Lime & Chert
3619	Lime
3630	Chert
3672	Lime & Chert
3727	Lime
3753	Lime-Cherty
3778	Chert Lime
3987	Shale
3987	T. D.

Well perforated @ 3617 - 3623'

Well Perforated @ 3262 - 3268'

No Plug

Cable Tool T.D. 4024'

RECEIVED
STATE CORPORATION COMMISSION

AUG 10 1965
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss:

I, Milton Glickman, of the Glickman Oil Company, upon oath state that the above and foregoing is a true and correct copy of the log of the Goering Well #1

Milton Glickman
Milton Glickman

Subscribed and sworn to before me this 30th June, 1960

Lorella Schanz
Lorella Schanz Notary Public

My Commission Expires: **November 19, 1963**