


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Reno County. Sec. 33 Twp. 25 Rge. 4 (E) W (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SW SE
Lease Owner B & R Drilling, Inc.
Lease Name Astle Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 5, 1950 19
Application for plugging filed October 16, 1950 Verbally 19
Application for plugging approved October 16, 1950 " 19
Plugging commenced October 17, 1950 19
Plugging completed October 19, 1950 19
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation Depth to top Bottom Total Depth of Well 4090 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	409'	None
				5 1/2"	4087'	4087'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugging Record

Filled hole with crushed rock to 4080',
dumped 6 sax cement at 4080' with dump bailer. Top of
cement 4040'. Filled hole with mud to 350', set rock
bridge, dumped 15 sax cement, top of cement 290'.
Filled with mud to 20', dumped 5 sax cement for cap.

RECEIVED
STATE CORPORATION COMMISSION
OCT 26 1950
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to B & R Drilling, Inc.
Address Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
Don Roberts (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) [Signature] Russell, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 24 th day of October, 1950
[Signature] Notary Public.

My commission expires 6-17-54

FILE SEC 53-TM-REO
BOOK PAGE 37-LINE 6

B & R Drilling, Inc.
Astle # 1

SE SW SE sec. 33-25S-4W
Reno County, Kansas

Total Depth: 4090'
Comm: 6-15-50
Comp: 7-5-50

Top: Viola Dolomite 4088(-2544)

Casing

8 5/8" Set @ 409'
5 1/2" Set @ 4087'

Cement

200 Sacks of Bulk
75 Sacks of Victor

Formation	Depth:
Surface Soil -Clay	15
Shale	115
Shale-Shell	275
Shale	375
Shale-Anhydrite	400
Shale-Shells of Anhydrite	493
Shale-Lime	3080
Lime	3215
Lime-Shale	3650
Mississippi Chat	3703
Lime-Chert	3765
Mississippi	3805
Lime	3892
Lime-Shale	4065
Shale	4090

STATE OF KANSAS)
)SS
RUSSELL COUNTY)

I hereby certify that the above information is true
and correct to the best of my knowledge.

RECEIVED
CORPORATION COMMISSION
OCT 26 1950
CONSERVATION DIVISION
Wright, Korbler

Subscribed and sworn to before me this 12th day of July, 1950.

Clara Linn
Notary Public

My commission expires: 6-17-54

