


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

T - 25 NORTH R - 4W



Locate well correctly on above  
Section Plat

Reno County, Sec. 33 Twp. 25 Rge. (E) 4 (W)  
Location as "NE/CNW/SW" or footage from lines SE - NE - SE  
Lease Owner Frank J. Black  
Lease Name \_\_\_\_\_ Last \_\_\_\_\_ Well No. 2  
Office Address McPherson, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed 8-24-49 19  
Application for plugging filed 2-2-59 19  
Application for plugging approved 2-3-59 19  
Plugging commenced 2-3-59 19  
Plugging completed 2-7-59 19  
Reason for abandonment of well or producing formation Non Commercial

If a producing well is abandoned, date of last production 1-31-59 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4096 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	375	Nonw
				5 1/2	4091	3370.64

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sanded to 4075' - dumped 5 sks cement - mudded hole to 250' - set 10' rock bridge - dumped 20 sks cement - mudded hole to 35' - set 5' rock bridge - dumped 10 sks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 20 1959  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor R & D Casing Pulling Company License # 236  
Address Box 569 Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF MCPHERSON, ss.  
Frank J. Black (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Frank J. Black*

(Address)

SUBSCRIBED AND SWORN TO before me this 19 day of Feb, 19 59

*Paul Nelson*  
Notary Public.

My commission expires Jan 10 - 1961

PLUGGING  
FILE SEC 33 T. 25 R. 4W  
BOOK PAGE 14 LINE 10


COPY

Company - PHILLIPS PETROLEUM COMPANY  
 Farm - Last No 2

SEC. 33 T. 25 R. 4W  
 SE NE SE

Total Depth. 4096  
 Comm. 6-22-49 Comp. 8-24-49  
 Shot or Treated.  
 Contractor.  
 Issued, 7-24-49

County. Ellsboro  
 KANSAS



CASING:

8" 350'  
 5" 4092'

Elevation. \_\_\_\_\_

Production. 413 bbls. oil and trace water.

Figures indicate bottom of formations.

redbed, shale, shells	164
sand, shale	375
sand, shale, salt	647
shale, anhydrite	1152
lime, shale	1565
shale, shells	1805
lime, shale	2416
lime	2703
lime, shale	2850
lime	3952
lime, shale	4080
lime	4096
Total depth	

Tops:	
Heebner	2635
Toronto	2651
Brown lime	2825
Lansing K. C.	2860
Mississippian	3634
Kinderhook	3974
Miscner	4075
Viola	4092

Viola, 4092-96, Poor to fair xlyn to slightly vugular porosity, no stain, fair oil taste in wet samples.

**PLUGGING**  
 FILE SEC. 33 T. 25 R. 4W  
 BOOK PAGE 14 LINE 16