


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Reno County. Sec. 33 Twp. 25S Rge. 4 (W)
Location as "NE/CNWKSWK" or footage from lines 330' fr. S & 330' fr. E, NE/4
Lease Owner Phillips Petroleum Company
Lease Name Cooley Well No. 3
Office Address Box 779, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed December 3, 19 49
Application for plugging filed September 5, 19 57
Application for plugging approved September 9, 19 57
Plugging commenced September 15, 19 57
Plugging completed September 18, 19 57
Reason for abandonment of well or producing formation Uneconomical to operate.

If a producing well is abandoned, date of last production September 9, 19 57
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Ruel Durkee
Producing formation Viola Depth to top 4096 Bottom NR Total Depth of Well 4099 1/2 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Heebner</u>	<u>Dry</u>	<u>2636</u>	<u>NR</u>	<u>8-5/8"</u>	<u>346'</u>	<u>None</u>
<u>Toronto</u>	<u>Dry</u>	<u>2655</u>	<u>NR</u>	<u>5-1/2"</u>	<u>4113'</u>	<u>3509'</u>
<u>Lansing-Kansas City</u>	<u>Dry</u>	<u>2862</u>	<u>NR</u>			
<u>Viola</u>	<u>oil</u>	<u>4096</u>	<u>4099 1/2</u>			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped sand 4099 1/2' to 4080'. Dumped 6 sx. cement to 4040'. Mudded hole to 310'. Set 10' rock bridge to 300'. Dumped 15 sx. cement to 255'. Mudded hole to 25'. Set 10' rock bridge to 15'. Dumped 5 sx. cement to base of cellar. Well plugged and abandoned 5:00 P.M. 9-18-57.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
A. J. Willis (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Box 779, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of September

My commission expires November 18, 1957

PLUGGING
FILE SEC 33 T. 25 R. 4W
BOOK PAGE 43 LINE 3

RECEIVED
STATE CORPORATION COMMISSION
SEP 21 1957
Notary Public.
CONSERVATION DIVISION
KANSAS

Phillips Petroleum Company EXPLORATION RECORD
 Cooley No. 3 - 330' from South line and 330' from East line, NE/4 Sec. 33-25S-4W,
 Reno County, Kansas

Lease Cooley

Well 3

Formation Name	Top	Base	Remarks
Shale	0	90	
Shale and shells	90	731	
Shale and anhydrite	731	1216	
Lime and shale	1216	1739	
Lime, shale and shells	1739	1954	
Lime and shale	1954	3100	
Lime	3100	3954	
Lime and shale	3954	4103 PB 4099½ TD	
<u>FORMATION TOPS:</u>			
Heebner	2636		
Toronto	2655		
Lansing-Kansas City	2862		
Viola	4096		

RECEIVED
 STATE CORPORATION COMMISSION

SEP 21 1957
 DIVISION

PLUGGING
 FILE SEC. 33 T. 25 R. 4W
 BOOK PAGE 43 LINE 3