

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-22,776-0000

LEASE NAME Zink

WELL NUMBER #1

1650 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 34 TWP. 25S RGE. 11W ~~65W~~ (W)

COUNTY Stafford

Date Well Completed 5-21-91
7:15 AM

Plugging Commenced 5-21-91

8:00 AM
Plugging Completed 5-21-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR RAMA Operating Company, Inc.

ADDRESS P. O. Box 159
Stafford, Kansas 67578

PHONE#(316) 234-5191 OPERATORS LICENSE NO. 3911

Character of Well D & A

(Oil, Gas, D&A SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-20-91 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached? Yes

Producing Formation Depth to Top Bottom T.O.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				10 3/4"	240'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Filled hole with heavy mud, 75 sacks at 870'; 75 sacks at 270'; 15 sacks at 40';
15 sacks in rathole and 10 sacks in mousehole. Used 60/40 Pozmix with 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142

Address P. O. Box 129
Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.

Richard L. Mead (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Richard L. Mead

(Address) Richard L. Mead, President
P. O. Box 129, Sterling, Kansas

SUBSCRIBED AND SWORN TO before me this 22nd day of May, 19 91



Agnes D. Wurst
Notary Public - Agnes D. Wurst

My Commission Expires: 4-26-93

RECEIVED
STATE CORPORATION COMMISSION

MAY 28 1991

CONSERVATION DIVISION
Wichita, Kansas

Form CP-4
Revised 07-87

STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - ZINK #1
Located: SW NE SE, Section 34-25S-11W, Stafford County,
Kansas

OWNER: Rama Operating Company, Inc.
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: May 14, 1991
COMPLETED: May 21, 1991

TOTAL DEPTH: 4182' Driller's T.D.
4182' Log T.D.

<u>LOG</u>	<u>CASING RECORD</u>
0 - 180 Surface Soil and Sand	Spud at 9:30 AM, 5-14-91. Drilled 240' 14 3/4" hole. Ran 6 joints 10 3/4", 40.50# new casing. 227.43' pipe set at 240' K.B. Cemented with 175 sacks 60/40 Pozmix with 2% gel and 3% cc. Plug down at 2:15 PM, 5-14-91, by Howco. Good returns to surface.
180 - 240 Shale	
240 - 1305 Shale	
1305 - 4182 Lime and Shale	Plugged.

Deviation Surveys: 1 1/2° at 1000'
1 1/2° at 3865'
1° at 4040'

RECEIVED
STATE CORPORATION COMMISSION

MAY 28 1991

CONSERVATION DIVISION
Wichita, Kansas