

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-22,805-0000

LEASE NAME Gamble

WELL NUMBER #1

4620 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 34 TWP. 25S RGE. 11 ~~EXX~~ (W)

COUNTY Stafford

Date Well Completed 9-30-91

11:00 PM

Plugging Commenced 9-29-91

12:30 AM

Plugging Completed 9-30-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR RAMA Operating Company, Inc.

P. O. Box 159

ADDRESS Stafford, Kansas 67578

PHONE# (316) 234-5191 OPERATORS LICENSE NO. _____

Character of Well _____

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on September 29, 1991 (date)

by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom T.O. 4210'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
				10 3/4"	240'	None

OCT 03 1991
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Filled hole with heavy mud. Heavy mud to 690' with 75 sacks at 690'; 75 sacks at 270'; 20 sacks at 60' to surface, 15 sacks in rathole. Used 60/40 Pozmix with 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142

Address P. O. Box 129
Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.

Richard L. Mead (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Richard L. Mead
Richard L. Mead, President
(Address) P. O. Box 129, Sterling, Kansas 67579

SUBSCRIBED AND SWORN TO before me this 1st day of October, 1991

Agnes D. Wurst
Agnes D. Wurst, Notary Public

My Commission Expires: 4-26-93



STERLING DRILLING COMPANY

BOX 129
STERLING, KANSAS 67579

October 1, 1991

RECEIVED
STATE CORPORATION COMMISSION

OCT 03 1991

CONSERVATION DIVISION
Wichita, Kansas

SAMPLE LOG - - - - - Gamble #1
located C-NE-NE Sec. 34, T 25S R 11W, Stafford County, Kansas

OWNER: RAMA Operating, Inc.
ROTARY DRILLING, CONTRACTOR: Sterling Drilling Company

COMMENCED: September 24, 1991
COMPLETED: September 30, 1991

TOTAL DEPTH: R.T.D. 4210'
L.T.D. 4210'

LOG

0' - 180'	Surface Soil & Sand
180' - 240'	Red Bed
240' - 330'	Red Bed
330' - 4210'	Shale & Lime

CASING RECORD

Spud at 8:00 a.m. 9-24-91
Drilled 240' of 14 3/4" hole
Ran 226.96' of 10 3/4" 40.5#
used casing, Set at 240' K.B.
cemented with 200 sacks of 60
X 40 pozmix with 2% gel. & 3%
CC. Plug down at 1:00 p.m.
9-24-91 by Howco. Returns to
surface. Drilled 9 7/8" hole
to 1000'.

DEVIATION SURVEYS

1 3/4° at 4070'
3/4° at 4210'