

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 5 1959  
CONSERVATION DIVISION  
Wichita, Kansas

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Reno  
Location: NW. SE. SW. Sec. 30 Twp. 25 Rge. 4 (E) (W) ✓  
Name of Field: \_\_\_\_\_ Total Depth: 4026'

I have this date completed supervision of plugging of:

Lease Name: Dole Well No. 1

Operator's Full Name: G. C. Smitherman

Complete Address: Box 627 Augusta Kans.

Plugging Contractor: Morgan Well Pulling

Address: 102 W. 18th St. Hutchinson License No. 43

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No ✓

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 9:30 Day 27 Month Oct. Year 1959

The above well was plugged as follows:  
J. D. 4026' - S. P. 8 5/8" - 109' - CWC. Perf. 4021-4022  
Bottom, sand to 4000' - 5 ac. with bailer  
Mud from 630' to 200'  
10" R. B. 200' - 20 ac.  
- R. B. 105' - 15 ac.  
R. B. 30' 5 ac.

Signed: Fred W. Harnfel  
Conservation Division Agent

Reviewed: J. Lewis Brock  
Field Supervisor

Remarks:

INVOICED  
DATE 1/11/60  
INV. NO. 341-w

DOLES #1

COMPANY: L. C. Smitherman - Oil Producer Location: NW SE SW, Sec 30-25-4  
 CONTRACTOR: L. C. Smitherman Drilling Co. Reno County, Kansas  
 Commenced: September 16, 1959 Elevation: 1537 DE  
 Completed: September 30, 1959 1539 RB  
 Casing: 298' of 8 5/8" Cem W/170 Skts.  
 4026' of 4 1/2" Casing Cem W/100 sacks.

FIGURES INDICATE BOTTOMS OF FORMATIONS:

0	245	Soil & Clay
245	540	Shale & Shells
540	840	Shale
840	1020	Lime & Shale
1020	1120	Lime & Shale
1120	1310	Lime & Shale
1310	1460	Lime & Shale
1460	1665	Shale & Lime Streaks
1665	1940	Shale & Lime
1940	2100	Shale & Lime
2100	2125	Lime & Shale
2125	2250	Shale & Lime
2250	2365	Lime & Shale
2365	2500	Lime & Shale
2500	2571	Lime & Shale
2571	2609	Lime
2609	2700	Lime & Shale
2700	2760	Lime & Shale
2760	2855	Shale & Lime Streaks
2855	2935	Lime (Kansas City)
2935	3035	Lime
3035	3116	Lime
3116	3166	Lime
3166	3264	Lime & Shale
3264	3352	Lime & Shale Breaks
3352	3422	Lime
3422	3469	Lime
3469	3560	Lime
3580	3600	Lime (Mississippi)
3600	3620	Chat (Mississippi)
3620	3630	Lime
3630	3669	Lime
3669	3697	Lime
3697	3727	Lime
3727	3748	Lime
3748	3786	Lime
3786	3805	Lime
3805	3829	Lime
3829	3843	Lime
3843	3862	Shale
3862	3892	Shale & Lime
3892	3950	Shale
3950	3991	Shale
3991	4016	Shale
4016	4026	Lime
4026		TOTAL DEPTH

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 OCT 21 1959  
 RECORDS SECTION DIVISION  
 Topeka, Kansas

This is to certify the above and foregoing to be a true and correct copy of the Log on the Doles #1 located in the NW SE SW, Section 30-25-4, Reno County, Kansas

L. C. SMITHERMAN DRILLING COMPANY

Subscribed and sworn to before me this 20th day of October, 1959.

(Notary Public)

My Commission expires March 31, 1962.