

KANSAS

FORM CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGEN'T REPORT

J. Lewis Breck
Administrator
245 North Water
Wichita, Ks. 67202

API Number 15 - - (of this well) ✓

Operator's Full Name Brougher Oil, Co.

Complete Address Drawer 1367, Great Bend, Ks. 67530

Lease Name Bell "A" Well No. 1-A

Location 12'E NW NE NW Sec. 3 Twp 25S Rge. 13 (E) (W) W

County Stafford Total Depth 4241

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

~~Other well in area to be plugged~~ The Loc-Depth-Well number is correct.

Plugging Contractor Kelso Casing Pulling.

Address Box 176, Chase, Ks. 67524 License No. 683

Operation Completed: Hour 11 Am. Day 10 Month 7 Year 1980

The Above well was plugged as follows:

264' 8 5/8" casing. 4 1/2" casing set at 4240' w/100 sax cement. Plug
back to 4198'-Top perforation at 3853' to 3861'-Howco mixed & pumped'
in 4 1/2" casing 35 sax common cement to 3430'-Pull 3405' casing-Howco
mixed & pumped 8 sax hulls-25 sax gel-100 sax 50/50 posmix cement w/4%
gel & 3% cc to top of casing. Shut in w/300# pressure.

RECEIVED
STATE CORPORATION COMMISSION
JUL 14 1980
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 7-15-80

INV. NO. 2587-W