

KANSAS

Form CP-3
Rev. 6-26-62STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORTRECEIVED
STATE CORPORATION COMMISSION

MAY 16 1966

CONSERVATION DIVISION
WICHITA, KANSASJ. P. Roberts
Administrator
500 Insurance Building
Wichita 2, KansasOperator's Full Name Hellar Drilling Company, Inc.Complete Address: 1014 Union Center Bldg., Wichita, KansasLease Name Halley "B" Well No. # 1Location NE NW NW Sec. 3 Twp. 25 Rge. 13 (E) (W) WCounty Stafford Total Depth 4246'Abandoned Oil Well Gas Well Input Well SWD Well D & A XOther well as hereafter indicated: Plugging Contractor: Hellar Drilling Company, Inc.Address: 1014 Union Center Bldg., Wichita, Kansas License No. Operation Completed: Hour 10:00AM Day 10th Month May Year 1966

The Above well was plugged as follows:

253' of 8 5/8" surface pipe, cement circulated with 250 sacks. Fluid
level in the hole was at 120'. 1st cementing plug and 1/2 sack of hulls
was pushed in fluid to 240', And cemented with 25 sacks, through the
drill pipe. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged with 1/2 sack of hulls on fluid at 40', and cemented
with 10 sacks to the base of the cellar. Rat hole bridged and cemented
with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging SupervisorDATE 5/16/66INV. NO. 3225-11