



KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 25 1964  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Beardmore Drilling Company

Complete Address: 827 Beacon Bldg., Wichita, Kansas

Lease Name Cornwell Well No. # 1

Location NE NW SW Sec. 4 Twp. 25 Rge. 13 (E) (W) W

County Stafford Total Depth 4025

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A      X     

Other well as hereafter indicated:     

Plugging Contractor: Hellar Drilling Company

Address: 1014 Union Center, Wichita, Kansas License No.     

Operation Completed: Hour 3:00AM Day 24th Month May Year 1964

The Above well was plugged as follows:

358' of 8 5/8" surface pipe, cemented with 275 sacks. Fluid level was  
up in the hole. 1st cementing plug and 1/2 sack hulls was pushed in fluid  
to 275', and cemented with 25 sacks, through the drill pipe. Hole was  
filled with drilling mud to 40', 2nd cementing plug, bridged solid  
with hulls, on fluid at 40', and cemented with 10 sacks to base of the  
cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 5/26/64  
INV. NO. 9213-W

Signed: Archie Elving  
Well Plugging Supervisor