

STATE OF KANSAS
STATE CORPORATION COMMISSION
101 S. Market, Room 2078
Wichita, KS 67202
KANSAS CORPORATION COMMISSION

WELL PLUGGING RECORD
K.A.R. 02-3-117

API NUMBER 15-185-22,993

LEASE NAME Helmer

WELL NUMBER 2-A

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 33 TWP. 25S RGE. 11W (E) or (W)

COUNTY Stafford

Date Well Completed

Plugging Commenced 12-6-99

Plugging Completed 12-9-98

DEC 10 1999

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

CONSERVATION DIVISION
LEASE OPERATOR LOTUS Operating Co. L.L.C.

ADDRESS 100 S. Main Suite 520 Wichita, Kansas 67202

PHONE (316) 262-1077 OPERATORS LICENSE NO. 31980

Character of Well Oil

(Oil, Gas, D&A, SHD, Input, Water Supply Well)

This plugging proposal was approved on (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4196

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				10-3/4"	273'	None
				5-1/2"	4195'	2000'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from feet to feet each side. Plugged off bottom with sand to 3820' and 5 sks. cement. Shot pipe @ 2500', 2300' & 2000'. Plugged well with 300# hulls, 10 sks. gel, 50 sks. cement, 10 sks gel, 100# hulls and 125 sks. cement, 60/40 pos, 6% gel.
Plugging complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Lotus Operating Co. L.L.C.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed therewith, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 9th day of December, 1999

[Signature]
Notary Public

My Commission Expires:



Form CP
Revised 05-

(2)