

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Reno County, Sec. 26 Twp. 25 Rge. 9W (E) (W)

Location as "NE/CNW/SW" or footage from lines SE SE SE

Lease Owner El Dorado Refining Company

Lease Name Mc Atee Well No. 1

Office Address Central Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed October 31 1956

Application for plugging filed October 31 1956

Application for plugging approved October 31 1956

Plugging commenced October 31 1956


Plugging completed October 31 1956

Reason for abandonment of well or producing formation oil in commercials  
quantity not available

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? \_\_\_\_\_

NORTH



Locate well correctly on above  
Section Plat

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4335 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	250'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with extra heavy rotary mud from total depth to 240'. Set #1 plug with 20 sacks cement. Filled hole with extra heavy rotary mud from plug #1 to 35'. Set #2 Plug at 35' with 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV - 7 1956  
11-7-56  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor Prime Drilling Company  
Address 814-16 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF Sedgwick, ss.  
R. R. MCNICOL (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R.R. McNicol  
814-16 Union Center, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 6th day of November, 19 56

My commission expires Sept. 30, 1959  
Darlene May Notary Public.

PLUGGING  
FILE SEC 26 T 25 R 9W  
BOOK PAGE 112 LINE 39

ROTARY DRILLING LOG

OPERATOR: El Dorado Refining Company  
 McAtee #1  
 Reno County, Kansas

CONTRACTOR: Prime Drilling Company  
 COMH: 10-15-56  
 COMP: 10-31-56

Formations:

Red Rock & Red Bed	200'
Red Bed	285'
Shale	675'
Gray Shale	985'
Anhydrite	1025'
Salt Shale & Lime	1315'
Lime	1910'
Lime & Shale	2390'
Shale & Sandy Lime	2450'
Shale & Lime	3210'
Lime	3405'
Lime & Chert	3452'
Lime	3555'
Lime & Cherty Lime	3630'
Lime	3685'
Lime & Cherty Lime	3729'
Lime	3780'
Lime & Shale	3842'
Miss. Chat	3897'
Lime & Chert	3915'
Miss. Lime & Chat	3935'
Lime & Shale	4150'
Lime Chert & Shale	4170'
Lime	4213'
Shale & Sand	4236'
Lime & Shale	4245'
Sandy Lime & Shale	4262'
Sand & Shale	4300'
Lime	4335'

Rotary Total Depth 4335'

Remarks: Set 8 5/8" surface casing  
 at 250' cemented with 190 sacks Pozmix,  
 2% C. C.

We Certify the above log is true and  
 correct to the best of our knowledge  
 and belief.

PRIME DRILLING COMPANY

R. R. Mc Nicol

RECEIVED  
 STATE CORPORATION COMMISSION  
 NOV 7 1956  
 CONSERVATION DIVISION  
 Wichita, Kansas

PLUGGING  
 FILE SEC 26 T 25 R 9W  
 BOOK PAGE 112 LINE 39