

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION

FORM CP-1

Rev. 03/92

130 S. Market, Room 2078  
Wichita, Kansas 67202

WELL PLUGGING APPLICATION FORM  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-185-23033,0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR RAMA Operating Co., Inc. KCC LICENSE # 3911  
(owner/company name) (operator's)

ADDRESS: P.O. Box 159 CITY: Stafford  
STATE: Kansas ZIP CODE: 67578 CONTACT PHONE: (316) 234-5191

LEASE: Zink WELL#: 2-34 Section 34 Township 25s Range 11w  
165' South of C Nw Nw Se SPOT LOCATION/QQQQ COUNTY: Stafford

2145 FEET (in exact footage) FROM S / N (circle one) LINE OF SECTION (NOT Lease Line)

2310 FEET (in exact footage) FROM E / W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ D&A XX SWD/ENHR WELL \_\_\_\_\_ Docket # \_\_\_\_\_  
CONDUCTOR CASING SIZE None SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS  
SURFACE CASING SIZE 10-3/4 SET AT 268' KB CEMENTED WITH 220 SACKS  
PRODUCTION CASING SIZE None SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS:  
ELEVATION 1818 G.L. 1827 K.B. T.D. 4223 P.BTD. \_\_\_\_\_ Anhydrite Depth 515'-535'  
(Stone Corral Formation)

CONDITION OF WELL: GOOD XX POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

PROPOSED METHOD OF PLUGGING:  
Heavy mud to 600' then 50 sacks, heavy mud to 300' then 75 sacks, heavy mud to 40' then 15 sacks,  
Using 60/40 Poz with 6% Gel. Plug rathole with 15 sacks and plug mousehole with 10 sacks.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes (YES,NO) IS ACO-1 FILED? ? (YES,NO)  
If not explain why? \_\_\_\_\_

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Name: Vaughn Thompson/Steve E. McClain Phone#: (316) 672-9508  
Address: P.O. Box 1006 City: Pratt State: Kansas

PLUGGING CONTRACTOR: Sterling Drilling Company KCC LICENSE #: 5142  
(company name) (contractor's)

Address: P.O. Box 1006 City: Pratt State: Kansas Zip 67124

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Plugged well at 8:00 pm on December 20, 1996

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY: Operator X Agent \_\_\_\_\_

DATE: 12/27/96 AUTHORIZED OPERATOR OR AGENT: \_\_\_\_\_  
(signature) Steve E. McClain, Agent for Operator

