


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Reno County, Sec. 12 Twp. 26s Rge. 6 W. (E) (W)

Location as "NE/CNW/SW" or footage from lines C NW SW

Lease Owner V. W. Wiggins

Lease Name Ruth Well No. I

Office Address P.O. Box 191 Mc Pherson, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed 5-2 1961

Application for plugging filed June 1962

Application for plugging approved June 1962

Plugging commenced July 5 1962

Plugging completed July 10 1962

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Justice

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4145' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				<u>5 1/2"</u>		<u>3099'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom of hole with rock. Rock from 3612' to 3580'. Dumped 5 sx of cement. Mudded hole to 255'. Set 10' of rock bridge. Dumped 20 sx of cement. Finished mudding hole to 40'. Set 10' of rock bridge. Dumped 10 sx of cement, filling to the bottom of the cellar/

RECEIVED
STATE CORPORATION COMMISSION
7-19-62
JUL 19 1962

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Art Lamb Casing Pulling Co.
Address P.O. Box 983 Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Reno, ss. Art Lamb

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art Lamb

2809 Kings Drive, Hutchinson, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 14 th day of July 1962

My commission expires January 5, 1966

Rudolph Lamb
Notary Public.

WELL DATA

Original Operator: Kewanee Oil Co.

Lease: Ruth

Loc.: C NW SW Sec. 12- 26S - 6W Reno Co.
Elev. 1500'

Well No. 1

Commenced: April 15 , 1961

Completed: May 2 , 1961

8 5/8" casing @ 282'

Lease acquired by Vaughn E. Wiggins , and Ruth No. 1 washed down October 16, 1961.

5 1/2" casing Cen. @ 4115' w/ 150 sacks.

FORMATION RECORD

0 - 293	Top Soil , clay , sashel & gravel
293 - 935	Shale & shells & sand
935 - 1086	Shale & sand
1086 - 1703	Shale & Lime
1703 - 1925	Shale & Sand
1925 - 2325	Shale , sand & lime
2325 - 2575	Shale & Lime
2525 - 2756	Lime & Shale
2756 - 2895	Sand & Lime
2895 - 3019	Lime w/ shale..
3019 - 3286	Lime , shale & sand
3286 - 3598	Lime & shale
3598 - 3690	Chert & Lime
3690 - 3818	Lime & Shale
3818 - 3990	Shale w/ Lime streaks
3990 - 3989	Shale & Lime
3989 - 4020	Lime & Shale
4020 - 4145	Lime

TD. 4145

RECEIVED
STATE CORPORATION COMMISSION
7-19-62
JUL 19 1962
CONSERVATION DIVISION
Wichita, Kansas

Plug Back to 3612

Perforated from 3598' to 3607'

3580 - 5
259 - 20
40 - 10