

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 130 S. Market, Room 2078  
 Wichita, KS 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-155-21,125-0000

LEASE NAME Betty Krehbiel

WELL NUMBER I

4950 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 12 TWP. 26S RGE. 6 (X) or (W)

COUNTY Reno

Date Well Completed 8/2/98

Plugging Commenced 8/3/98

Plugging Completed 8/4/98

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR W. R. Allam

ADDRESS P.O. Box 2325, Hutchinson, Ks. 67504

PHONE#( 316) 465-2337 OPERATORS LICENSE NO. 5808

Character of Well non-profitable

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8/2/98 (date)

by Jack Luthi (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation Mississippi Depth to Top 3600 Bottom 3620 T.O. 4020

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface Pipe		0	218	8 5/8	216	none
Viola	oil & water	3964	3974	5 1/2	4020	2400'
Mississippi	oil & water	3613	3620	plug set at		3696
KC	water	3298	3302	plug set at		3502
KC	water	3251	3258	plug set at		3275

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set  
Dumped 5 sacks on the top of plug at 3502 - shot pipe at 2500' - pulled 1150' of casing  
spotted 35 sacks at 1150' - pulled casing to 650 - spotted 35 sacks of cement - pulled  
casing to 270' - circulated cement to surface - finished pulling casing - put in 1 1/2 yds.  
of red-MLX on 8/10/98

Name of Plugging Contractor Sunflower Well Service, Inc. License No. 3280

Address P.O. Box 341, Cantoni, Ks.

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: W. R. Allam

STATE OF Kansas COUNTY OF Reno, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) W. R. Allam

(Address) P.O. Box 2325, Hutchinson, KS

SUBSCRIBED AND SWORN TO before me this 14<sup>th</sup> day of August, 19 98

Cheri L. Heim  
 Notary Public

My Commission Expires: March 31, 1999

