

LEASE NAME Betty Krehbiel

WELL NUMBER 2

3960 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 12 TWP. 26 RGE. 6 ^{XX} (E) or (W)

COUNTY Reno

Date Well Completed 7/20/90

Plugging Commenced 1/23/92

Plugging Completed 1/27/92

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR W. R. Allam, Jr.

ADDRESS P.O. Box 2325, Hutchinson, Ks.

PHONE# (316) 465 2337 OPERATORS LICENSE NO. 5808

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1/20/92 (date)

by James Martin (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Mississippi Depth to Top 3622 Bottom 3646 T.D. 3650

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Mississippi		3622	3646	5 1/2	4024	3140

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Ran dump bailer in & found T.D. at 3646. Pushed plug down to 3650

and dumped 78 gallons of sand. Top of sand at 3572 and dumped 5 sacks of cement on bottom with dump bailer. Shot pipe off at 3140. Then pulled 48 jts. and spotted 35 sacks of cement at 950. Pulled 10 jts. & spotted 35 sacks at 500. Pulled 5 jts and tried to circulate cement from 250 to surface. Did not circulate. Filled hole to surface with cement.

Name of Plugging Contractor Sunflower Well Service, Inc. License No. 30280

Address Box 343,

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: W. R. Allam, Jr.

STATE OF Kansas COUNTY OF Reno, ss.

W. R. Allam, Jr. (~~Employer or Operator~~) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

RECEIVED
 STATE CORPORATION COMMISSION
3-17-92
 MAR 17 1992

(Signature) W. R. Allam Jr.

(Address) P.O. Box 2325, Hutchinson, Ks.

SUBSCRIBED AND SWORN TO before me this 16th day of MARCH, 19 92

[Signature]
 Notary Public

My Commission Expires:
 USE ONLY ONE SIDE OF EACH FORM

NOTARY PUBLIC - State of Kansas
 H. H. STECHER
 My Appt. Exp. 12/29/92

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER _____ (of this well).
(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR _____ OPERATOR'S LICENSE NO. _____

ADDRESS _____ PHONE # () _____

LEASE (FARM) _____ WELL NO. _____ WELL LOCATION _____ COUNTY _____

SEC. _____ TWP. _____ RGE. _____ (E) or (W) TOTAL DEPTH _____ PLUG BACK TD _____

Check One:

OIL WELL _____ GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

PERFORATED AT _____

CONDITION OF WELL: GOOD _____ POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING _____

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? _____
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE
RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

_____ PHONE # () _____

ADDRESS _____

PLUGGING CONTRACTOR _____ LICENSE NO. _____

ADDRESS _____ PHONE # () _____

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

USE ONLY ONE SIDE OF EACH FORM

SIGNED: _____
(Operator or Agent)

DATE: _____

ORIGINAL

TORNADO DRILLING, INC.
P.O. BOX 37
CANTON, KANSAS 67428
July 30, 1990

COMPANY: W. R. ALLAM

CONTRACTOR: TORNADO DRILLING, INC.

FARM: BETTY K. KREHBIEL # 2

LOCATION: 3910' FSL & 4900' FEL OF SECTION
12-26S-6W, RENO COUNTY, KANSAS

COMMENCED: JULY 11, 1990

COMPLETED: JULY 20, 1990

ELEVATION: 1524 GL. 1529 K.B.

0	to	75	Soil, Sand & clay
75	to	230	Lime
230	to	1085	Shale & Lime
1085	to	2075	Lime & Shale
2075	to	2910	Shale
2910	to	3517	Lime
3517	to	3624	Shale
3624	to	3829	Mississippi DST #1 3560-3629
3829	to	3970	Shale Misrun-Packer seat failure
3970	to	4025	Lime DST #2 3490-3629
		4025	Rotary Total Depth Rec 200' mud

Drill 12½" hole to 230'. Run new 20# 8-5/8" surface casing to 220'. Cement with 125 sacks 60/40 Pozmix and 60 sacks common with 2% C.C. Plug down at 9:30 P.M., July 11, 1990. Drill 7-7/8" hole to Rotary Total Depth of 4025'. Run 5½" 15.5# used casing and cement at 4024' with 175 sacks 60/40 Pozmix, .75% CFR-3, 5# gilsonite, .125# flowseal and 10% salt. Plug down at 1:30 A.M., July 21, 1990. Released rig.


OCT 12 1990
10-12-90

CERTIFICATE

I, Terry P. Bandy, President of Tornado Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Betty K. Krehbiel #2 located on the 3910' FSL and 4900' FEL of Section 12-26S-6W, Reno County, Kansas as is reflected by the files of Tornado Drilling, Inc.

Terry P. Bandy
Terry P. Bandy, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 30th day of July, 1990.



Cynthia G. Reimer
Cynthia G. Reimer - Notary Public