

15-155-20822-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Reno SEC. 16 TWP. 26S RGE. 8W E/W

Location as in quarters or footage from lines:

1980 Ft. from North Line and 330' from West Line

		6	

Lease Owner Reynold Lubbers
 Lease Name Lubbers Well No. #1
 Office Address 6555 S. Lewis Ave - Tulsa, Oklahoma 74136
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry
 Date Well Completed September 11, 1981
 Application for plugging filed September 13, 1982
 Plugging commenced 10-29-82
 Plugging completed 10-29-82
 Reason for abandonment of well or producing formation Non Commercial

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie

Producing formation Kansas City/Lansing Depth to top 3296' bottom T.D. 3910'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
<u>Kansas City/Lansing</u>	<u>Oil & Water</u>	<u>3296'</u>		<u>4 1/2"</u>	<u>3,900'</u>	<u>2,064'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from 3330 feet to feet for each plug set.

<u>9/22</u>	<u>Rig Up Star, Ran and set a Baker 4 1/2" Model P Cast Iron Bridge Plug. at 3330. Dumped 50 ft. of Cemenet on top of Cast Iron Bridge Plug.</u>
<u>10/4</u>	<u>Moved in on location and worked pipe.</u>
<u>10/5</u>	<u>Shot pipe to 2064 ft. Pulled 51 jts. of Casing.</u>
<u>10/6</u>	<u>Moved off of location, and pulled a total of 2063.66 ft of Casing</u>
<u>10/29</u>	<u>Rig Up Dowell and set 25 sacks-of-gelled w/ 6 sacks of Cotton hulls. Pumped 125 sacks of Class A Cement w/ 3% CC. Well Plugged.</u>

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lillard Casing Pulling, Inc.

STATE OF Oklahoma COUNTY OF Tulsa, ss./ Secretary
Vulcan Energy Corporation (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) David Justice
6555 S. Lewis Avenue Secretary
Tulsa, OK 74136 (Address)

SUBSCRIBED AND SWORN TO before me this 4th day of January, 1983

My Commission expires: 3-13-83

Notary Public.

JAN 10 1983

Wichita, Kansas

1-10-83