

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Reno SEC. 17 TWP. 26S RGE. 8W E/W
Location as in quarters or footage from lines:
1980' from North Line and 1980' from East Line

		17	

Lease Owner Patricia Billings and Robert G. Billings & Dorothy Kelman
Lease Name Billings Well No. #1
Office Address 6555 S. Lewis Avenue
Character of Well (Completed as Oil, Gas or Dry Hole): Dry
Date Well Completed 2-1-82
Application for plugging filed 9-13-82
Plugging commenced 10-29-82
Plugging completed 10-29-82
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Dry
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie
Producing formation None Depth to top _____ bottom _____ T.D. 3890'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Kansas City/Lansing	Water	3293'		4 1/2"	3890'	1981

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

- 9/22 Rig up Star Jet, Ran and set a 4 1/2" Model P Cast Iron Bridge Plug at 3230. Dumped 50 ft. of cement on top of Cast Iron Bridge Plug.
- 9/28 Moved onto location and rigged up.
- 9/29 Tagged plug at 3310. Finished rigging up.
- 9/30 Shot pipe at 2539, and at 1974. Pulled 1700 ft. of casing.
- 10/1 Pulled 274 ft. of casing and rigged down. Pulled a total of 1980.78 ft.
- 10/29 Rigged up Dowell and set 25 sacks of gelled w/ 6 sacks of cotton hulls. Pumped 125 sacks of Class A Cement w/ 3% CC.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lillard Casing Pulling, Inc.

STATE OF Oklahoma COUNTY OF Tulsa, ss. /Secretary
Vulcan Energy Corporation (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) David Justice
Secretary
6555 S. Lewis Avenue
Tulsa, OK. 74136
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of January, 19 83

My Commission expires: 3-13-83

J. Sandrien
Notary Public.
STATE OF KANSAS

JAN 10 1983 1-10-83