


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Reno County, Sec. 7 Twp. 26 Rge. 6 (E) (W)

Location as "NE/CNW/SW" or footage from lines NW/4 NE/4 SW/4
Lease Owner Midstates Oil Corporation
Lease Name Siebert "C" Well No. 1
Office Address 518 National Bank of Tulsa Bldg., Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 19, 19 53
Application for plugging filed July 20, 19 53
Application for plugging approved Verbal July 19, 19 53
Plugging commenced July 19, 19 53
Plugging completed July 20, 19 53
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. S. S. Greider
Producing formation None Depth to top Bottom Total Depth of Well 4215 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	399'	8-5/8"	399'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole from bottom to 399' from surface with heavy mud. Bridged - 15 sacks of cement plug. Filled with heavy mud to within 30' of ground surface. 30' down to ground surface, 10 sacks of cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barnett Drilling, Inc.
Address First National Bldg., Wichita, Kansas

STATE OF OKLAHOMA, COUNTY OF TULSA, ss.
W. H. Barclay (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. H. Barclay
518 N.B.T. Bldg., Tulsa, Oklahoma (Address)

SUBSCRIBED AND SWORN TO before me this 31 day of July, 1953

My commission expires My Commission Expires March 21, 1955

RECEIVED
BARNETT DRILLING, INC.
CORPORATION COMMISSION
Notary Public.

PLUGGING
FILE SEC 2 T 26 R 6W
BOOK PAGE 116 LINE 6

AUG - 1 1953
8-1-53
CONSERVATION DIVISION
Wichita Kansas

WELL RECORD

PRODUCER: Midstates Oil Corp., 518 National Bank of Tulsa Bldg., Tulsa, Oklahoma

FARM: Seibert "C" WELL NO: 1 FIELD: Wildcat

LOCATION: 330' S of N Line and 1650' E of W Line of Sec. 7-26S-6W, Reno County, Kansas

DRILLING BEGAN: June 26, 1953 DRILLING COMPLETED: July 20, 1953

ELEVATION: K.B. 1585'

CASING RECORD

Size	Where Set	Number of Sacks of Cement
8-5/8" OD 24 & 32#	399'	300'

<u>Top</u>	<u>Bottom</u>	<u>Formation</u>
0	225	Sand & Shale
225	1000	Shale
1000	2530	Shale & Lime
2530	2815	Lime
2815	2935	Lime & Shale
2935	3025	Shale & Lime
3025	3440	Lime
3440	3475	Lime & Shale
3475	3527	Lime
3527	3710	Lime & Shale
3710	3745	Lime & shale
3745	3775	Lime & shale
3775	3815	Lime
3815	3825	Hard Lime
3825	3860	Lime
3860	3970	Lime & shale
3970	4070	Lime
4070	4080	Sand & shale
4080	4145	Lime
4145	4165	Lime & shale
4165	4215	Lime
	4215	Total Depth

