

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

15-155-21151-0000

API NUMBER ~~15-077-217219~~

LEASE NAME Graber Trust #1

WELL NUMBER #1

495 Ft. from S Section Line

4785 Ft. from E Section Line

SEC. 1 TWP. 26 RGE. 6 (X) or (W)

COUNTY Reno

Date Well Completed 12/21/90

Plugging Commenced 1/29/92

Plugging Completed 9/30/92

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR W. R. Allam, Jr.

ADDRESS P.O. Box 2325, Hutchinson, Ks. 67504

PHONE# (316) 465 2337 OPERATORS LICENSE NO. 5808

Character of Well \_\_\_\_\_

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9/14/92 (date)

by David Swiddiams (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? \_\_\_\_\_

Producing Formation Mississippi Depth to Top 3609 Bottom 3615 T.D.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Misener	oil/water	3971	3978	5 1/2"	4034	3096'
Mississippi	oil/water	3605	3615	5 1/2"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 9 feet to 9 feet each set.

Sanded to 3550' & dumped 5 sx cmt - shot & pulled

5 1/2" from 3096' to 1000' - spotted 35 sx cmt - pulled

5 1/2" to 550' & spotted 35 sx cmt - pulled 5 1/2" to

300' & circ to surf - topped off well

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sunflower Well Service License No. 30280

Address P.O. Box 341, Canton, Ks. 67428

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: W.R. Allam, Jr., P.O. Box 2325

STATE OF \_\_\_\_\_ COUNTY OF \_\_\_\_\_, ss.


(Employee of Operator) or (Operator's Agent)  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) W.R. Allam Jr.

(Address) Box 2325 Hutchinson, Ks.

SUBSCRIBED AND SWORN TO before me this 4<sup>th</sup> day of July, 19 92

My Commission Expires \_\_\_\_\_



Notary Public

RECEIVED  
 STATE CORPORATION COMMISSION

DEC 11 1992  
 12-11-92

RECEIVED  
KANSAS CORPORATION COMMISSION

TORNADO DRILLING, INC.  
P.O. BOX 37  
CANTON, KANSAS 67428

OCT 1 1992  
10-1-92  
CONSERVATION DIVISION  
WICHITA, KS

December 28, 1990

COMPANY: W.R. ALLAM

CONTRACTOR: TORNADO DRILLING, INC.

FARM: GRABER TRUST #1

LOCATION: 495' FSL & 4785' FEL SECTION  
1-26S-6W, RENO COUNTY, KANSAS

COMMENCED: DECEMBER 10, 1990

COMPLETED: DECEMBER 21, 1990


ELEVATION: 1510 GL. 1515 K.B.

0	to	25	Sand	
25	to	950	Shale & Lime	
950	to	1057	Shale	
1057	to	2910	Shale & Lime	
2910	to	3615	Lime	
3615	to	3619	Mississippi	DST #1 3606'-3619'
3619	to	3795	Mississippi	
3795	to	3850	Kinderhook	
3850	to	3975	Shale	
3975	to	3984	Misener	DST #2 3977'-3984'
3984	to	4010	Viola	
4010	to	4035	Simpson	
		4035	Rotary Total Depth	

Drill 12 1/2" hole to 228'. Run 222.94' New 8-5/8" surface casing set at 220'. Cemented with 120 sacks 40/60 Pozmix 3% CC, 60 sacks common 3% CC. Plug down at 3:00 A.M., December 11, 1990. Drill 7-7/8" hole to rotary total depth of 4035'. Run 4039' used 5 1/2" casing cemented at 4034' with 150 sacks 60/40 Pozmix, 10% salt, 5# gilsonite, 3/4% CFR3, 1/8# flowseal. Plug down at 9:15 P.M., December 21, 1990. Released rig.

CERTIFICATE

I, Terry P. Bandy, President of Tornado Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Graber Trust #1 located on the 495' FSL and 4785' FEL of Section 1-26S-6W, Reno County, Kansas as is reflected by the files of Tornado Drilling, Inc.

  
Terry P. Bandy, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 28th day of December, 1990