


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

## WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Reno County. Sec. 11 Twp. 25 Rge. 5 ~~XX~~ (W)  
Location as "NE/CNW/SW" or footage from lines NE/4 NW/4 SW/4  
Lease Owner A. Scott Ritchie  
Lease Name POPP "A" Well No. 1  
Office Address 352 North Broadway, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed December 1, 1963  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced December 1, 1963 1963  
Plugging completed December 1, 1963  
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert J. Toman, Holyrood, Kansas  
Producing formation Depth to top Bottom Total Depth of Well Feet  
Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

## CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Clay & Shale		0	100			
Shale & Lime Shells		100	227	10 3/4	227	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud to 220 ft. and set plug,  
put 20 sacks cement on top. Filled with mud  
to 20 ft. and put 10 sacks cement on top. 2  
sacks in rathole. Plug down at 5:00 P.M.,  
December 1, 1963.

RECEIVED  
STATE CORPORATION COMMISSION

DEC 18 1963

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Blackstone Drilling, Inc.  
Address Box # 455, McPherson, Kansas

STATE OF Kansas, COUNTY OF Reno, ss.

A. Scott Ritchie (employer of record) operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

352 North Broadway, Wichita, Kansas - 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 9<sup>th</sup> day of December, 1968

My commission expires

12-18-68

Notary Public.





# Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone CH-1-1250

McPHERSON • KANSAS

67460

RECEIVED  
STATE OIL & GAS COMMISSION

AUG 25 1966

December 2, 1963

COMPANY: A. SCOTT RITCHIE  
CONTRACTOR: BLACKSTONE DRILLING, INC.  
FARM: POPP "A" #1  
LOCATION: NE/4 NW/4 SW/4, Sec. 11-25-5W,  
Reno County, Kansas  
COMMENCED: November 17, 1963  
COMPLETED: December 1, 1963  
ELEVATION: 1550 K.B.

0	to	100	Clay & Shale
100	to	227	Shale & Lime Shells
227	to	400	Lime & Shale
400	to	625	Shale & Lime Shells
625	to	730	Anhydrite
730	to	985	Lime & Shale
985	to	1160	Shale & Lime
1160	to	1500	Lime & Shale
1500	to	1803	Shale & Lime
1803	to	1930	Lime & Shale
1930	to	2130	Shale & Lime
2130	to	2300	Lime & Shale
2300	to	2525	Lime
2525	to	2670	Lime, Shale & Sand
2670	to	2800	Lime & Shale
2800	to	3075	Lime
3075	to	3085	Lime & Shale
3085	to	3199	Lime
3199	to	3440	Lime & Shale
3440	to	3491	Shale & Lime
3491	to	3565	Mississippi
3565	to	3635	Chert & Lime
3635	to	3668	Lime & Chert
3668	to	3708	Lime
3708	to	3921	Shale
3921	to	4014	Viola Lime
4014	to	4033	Sand
4033	to	4052	Arbuckle . . . . . T.D.

Cut 15 1/4 in. hole to 225ft. & run 227 ft. of 10 3/4 in. surface pipe, cemented with 150 sacks cement on bottom at 225ft., 3% Gel & 2% calcium chloride. Plug down at 8:15 P.M., Nov. 17, 1963. Cut 7 7/8 in. hole to 4052ft. Hole dry and abandoned. Filled hole with mud to 220ft. & set plug, put 20 sacks cement on top. Filled with mud to 20ft. and put 10 sacks cement on top. 2 sacks cement in rat hole. Plug down at 5:00 P.M., December 1, 1963, by Gilbert J. Toman, State Plugger, Holyrood, Kansas.

TOPS: Heebner - 2546' Toronto - 2568' Douglas Shale - 2578' Douglas Sand - 2710'  
Lansing K.C. - 2765' Base K.C. - 3223' Cherokee - 3350' Mississippi Chert - 3494'  
Mississippi Lime - 3551' Kinderhook Shale - 3708' Maquoketa - 3869'  
Viola - 3923' Simpson - 3943' Arbuckle - 4035'

Measurements taken from K.B.

## CERTIFICATE

I, H. J. Plouffe, president of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Popp "A" #1, located on the NE NW SW of Sec. 11-25-5W, Reno County, Kansas as reflected by the files of Blackstone Drilling, Inc.

H. J. Plouffe, President

Subscribed and sworn to before me a Notary Public within and for McPherson County, Kansas this 2nd day of December, 1963.

Ruth McVay - Notary Public

My Commission Expires: December 18, 1965.