


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Kingman County. Sec. 1 Twp. 28S Rge. (E) 6 (W)
Location as "NE/CNW%SW%" or footage from lines. E SE NE
Lease Owner Pickrell Drilling Company
Lease Name Meng A Well No. 1
Office Address 705 4th Nat'l Bldg, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 31 1962
Application for plugging filed August 31 1962
Application for plugging approved August 31 1962
Plugging commenced August 31 1962
Plugging completed August 31 1962
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4230 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|-------|--------|------------|
| | | | | 8 5/8 | 213' | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 180'. Set Plug. Cemented with 20 sacks cement. Heavy mud to 35'. Set Plug. Cemented with 10 sacks to bottom of cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
9-10-62
SEP 10 1962
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company
Address 705 Fourth National Bank Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
C. W. SEBITS (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts
705 4th Nat'l Bldg, Wichita 2, Ks.
(Address)

SUBSCRIBED AND SWORN to before me this 4th day of September, 1962

Maxine Blackman
Maxine Blackman Notary Public.

My commission expires June 21, 1966



ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
705 Fourth Natl Bank Bldg.
Wichita 2, Kansas

Rotary Drilling Commenced: 8-18-62

Rotary Drilling Completed: 8-31-62

LOCATION: Meng "A" #1 SE NE 1-28S-6W
Kingman County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: (6 jts) 8 5/8" Surface Casing set at 213' cemented with 155 sacks cement. Circulated. Completed 8:30 P.M. 8-18-62. No oil string run. D & A.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

| | | | |
|------|---------------------|------------------------|-------|
| 35 | Red Rock | | |
| 170 | Shale | Circulated for Samples | |
| 214 | Red Rock | 3375' = | 3805' |
| 409 | Blue Shale | 3380" | 4115' |
| 910 | Shale, shell & Lime | 3410' | 4135" |
| 1175 | Shale & Lime | 3770" | 4141" |
| 1390 | Lime | 3780' | 4145" |
| 1590 | Lime & Shale | 3795' | 4195' |
| 3095 | Lime | | 4230' |
| 3630 | Lime & Shale | | |
| 3780 | Chat | Slope Test | |
| 3805 | Mississippian | 2200' | |
| 4062 | Miss. & Shale | 2700' | |
| 4115 | Kinderhook | 3200' | |
| 4158 | Lime | 3700' | |
| 4199 | Viola & Simpson | | |
| 4230 | Simpson R.T.D. | S. L. M. | |
| | | 2520' | |
| | | 3095' | |
| | | 3630' | |
| | | 4158' | |

RECEIVED
STATE CORPORATION COMMISSION
SEP 10 1962
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By: C. W. Sebitts, Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.

On this 4th day of September, 19 62, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. SEBITTS to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: June 21, 1966

Maxine Blackman
Notary Public