

State of Kansas

FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

February 7, 1964 **RECEIVED**
STATE CORPORATION COMMISSION

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

FEB 10 1964
2-10-64
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Leonard Reed of Terrel Drilling & Producing has this date requested permission to plug the following described well:

Mr. Reed guarantees payment of the plugging fee.

Operator's full Name: Fred B. & Phillip F. Anshutz

Complete Address: 1521 Wichita Plaza, Wichita, Kansas

Lease Name: Kelman Well No. 1

Location: C NW NW Sec. 9 Twp. 26 Rge. 8 (E) (W) X

County Reno Total Depth 3330' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Reed was instructed to plug the well as follows:

Fill hole with mud to 180'. Set hull bridge at 180' and cement with 40 sacks through drill pipe. Fill hole with mud to 40'. Push plug and $\frac{1}{4}$ sack hulls to 40' and cap hole with 10 sacks cement.

Bridge rathole, and cement with 2 sacks.

Orders by Archie Elving

Very truly yours,