

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

November 28, 1975

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Jim Gallagher of Gabbert-Jones, Inc. has this date requested permission to plug the following described well:

Mr. Gallagher guarantees payment of the plugging fee.

Operator's full Name: O. A. Sutton

Complete Address: 800 Sutton Place, Wichita, Kansas 67202

Lease Name: Voran Well No. 1

Location: C SE NE Sec. 22 Twp. 26 Rge. 6 ~~(E)~~ (W) X

County: Reno Total Depth 4225' Oil Well         

Gas Well          Input Well          SWD Well          D & A X Lost Hole         

Mr. Gallagher was instructed to plug the well as follows:

Fill hole with mud. Pump 40 sacks cement through drill pipe

at 450'. Pump 25 sacks cement through drill pipe at 250'.

Push plug and 1/2 sack hulls to 40' and cap hole with 10 sack

cement. Bridge rathole and cement with 2 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 3 1975  
12-3-75  
CONSERVATION DIVISION  
Wichita, Kansas

Very truly yours,

Conservation Division Agent