



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

JEWEL M. OGDEN, Director

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 7-13-62
 JUL 13 1962

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

I have this date 7 - 4 - 1962, 1961, authorized the following plugging operation:

Operator's full Name: Vaughn E. Wiggins

Complete Address: 205 Mills Bldg., McPherson, Kansas

Lease Name: Ruth Well No. 1

Location: Gen. NW SW Sec. 12 Twp. 26S Rge. 6 (E)(W) X

County: Reno Total Depth: 4145'

Oil Well Gas Well Input Well SWD Well

D & A Other well as hereafter indicated:

Abandoned Oil Well

Operator was instructed to plug well as follows:

5 1/8 pipe perforated between 3598' and 3612'. Sanded back to 3580' and 5 sacks cement as plug. 282' of surface pipe. Hole filled with mud to 250' with 10' rock bridge and 20 sacks cement. Filled to 40' with mud. Rock bridge and 10 sacks cement to bottom of cellar.

Very truly yours,

H. M. Ogden

