

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

November 2, 1978

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

NOV 21 1978
11-21-78
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Janze of Rains + Williamson Oil Co. has this date requested permission to plug the following described well:

Mr. Janze guarantees payment of the plugging fee.

Operator's full Name: Price Exploration Company

Complete Address: 814 Mayo Bldg., Tulsa, Oklahoma

Lease Name: Kellogg Well No. 1

Location: NE SW SW Sec. 15 Twp. 26 Rge. 8 ~~(E)~~ (W) X

County: Reno Total Depth 4000' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Janze was instructed to plug the well as follows:

8 5/8" - 241' w/200 sacks cement. Fill hole with mud. Pump
40 sacks cement through drill pipe at 500'. Pump 25
sacks cement through drill pipe at 230'. Push plug and
1/2 sack hulls to 40' and cap hole with 10 sacks cement.
Bridge rathole and cement with 2 sacks cement.

Very truly yours,

Conservation Division Agent