

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

April 12, 1974

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
APR 17 1974  
4-17-74  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Johnny Crowe of Da-Mac Drilling Co. has this

date requested permission to plug the following described well:

Mr. Crowe guarantees payment of the plugging fee.

Operator's full Name: Marsh Oil Assoc.

Complete Address: 595 Madison Ave, New York, New York

Lease Name: J. H. Graber Well No. 1

Location: SE SW Sec. 1 Twp. 26 Rge. 6 XX (E) (W) X

County: Reno Total Depth 3990' Oil Well

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Crowe was instructed to plug the well as follows:


Fill hole with mud. Push plug to 400' and pump 40 sacks cement through

drill pipe at 400'. Pump 25 sacks cement through drill pipe at 250'.

Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement.

Bridge rathole and cement with 2 sacks cement.

Very truly yours,

  
Conservation Division Agent