

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dec. 19, 1962.

RECEIVED  
 STATE CORPORATION COMMISSION

DEC 27 1962  
 12-27-62  
 CONSERVATION DIVISION  
 Wichita, Kansas

Dear Sir:

Mr. Bill Neal of Leben Drilling Co. has this  
 date requested permission to plug the following described well:

Mr. Bill Neal guarantees payment of the plugging fee.

Operator's full Name: Leben Drilling Co.

Complete Address: 905 Central Bldg. Wichita, Kansas.

Lease Name: H. H. Tonn "C" #1 Well No. #1

Location: C-SE-SW Sec. 35 Twp. 25S Rge. 5 (E) (W) X

County Reno County. Total Depth 4225' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Bill Neal was instructed to plug the well as follows:

243' of 8 5/8" surface pipe circulated with cement. Hole  
filled to 180' with heavy drill mud, 1 sack hulls, 1st  
cementing plug and 20 sacks cement. Hole filled to 40' with  
heavy drill mud, 1 sack hulls, 2nd cementing plug and 10  
sacks cement to base of cellar. Rat hole bridged and 2 sacks  
cement.

Very truly yours,

Herbert J. Gustafson  
 Conservation Division Agent