



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM

(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

SEP 4 1962
 9-4-62
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

I have this date 8 - 31 - 62, 1962, authorized
 the following plugging operation:

Operator's full Name: Pickrell Drilling Co.
 Complete Address: 705 Fourth Nat'l Bank Bldg. Wichita, Kansas
 Lease Name: Meng Well No. 1
 Location: C of SE NE Sec. 1 Twp. 28 Rge. 6 (E) (W) X
 County Kingman Total Depth 4230'
 Oil Well Gas Well Input Well SWD Well D & A X
 Other well as hereafter indicated: _____

Operator was instructed to plug well as follows:

214' of 8-5/8" surface pipe circulated with cement. Hole
filled to 180' with heavy drilling mud, 1/2 sack hulls, 1st
cementing plug and 20 sacks cement. Hole filled to 35'
with heavy drilling mud, 1/2 sack hulls, 2nd cementing plug
and 10 sacks cement to base of cellar. Rathole bridged and
 2 sacks cement.

Very truly yours,

Herman Justus
 Conservation Division Agent