

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-22776-00-01
Spot: SWSESW Sec/Twnshp/Rge: 34-25S-11W
1650 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: ZINK Well Number: 1 OWW
County: STAFFORD Total Vertical Depth: 4182 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S. MAIN
STAFFORD, KS 67578

Conductor Pipe: Size feet:
Surface Casing: Size 10.75 feet: 227 WITH 175 SX CMT
Production: Size 5.5 feet: 4175 WITH 100 SX CMT
Liner: Size feet: \$135.92

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/20/2001 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed Plugging Method: SAND TO 4125' & 5 SX CMT. 1ST PLUG AT 600' WITH 50 SX CMT. 2ND PLUG AT 260' WITH 75 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 08/20/2001 3:50 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

OPEN HOLE 4175-4182'. SAND TO 4125' & 5 SX CMT. PUMPED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 600' WITH 50 SX CMT. 2ND PLUG AT 260' WITH 75 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT.

RECEIVED

AUG 27 2001

KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2100' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

INVOICED

DATE 8-28-01

INV. NO. 2002060293

AUG 24 2001

Form CP-2/3