

1052359

TO: STATE CORPORATION COMMISSION

API NUMBER 15-185-22,993 --00-00
C S/2 SW NE SEC. 33, T 25 S, R 11 W

CONSERVATION DIVISION - PLUGGING SECTION 2310 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1980 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME HELMER WELL # 2-A

TECHNICIAN'S PLUGGING REPORT COUNTY STAFFORD

OPERATOR LICENSE # 31980 WELL TOTAL DEPTH 4196 FEET

OPERATOR: LOTUS OPERATING CO. L.L.C. PRODUCTION CSG: SIZE 5 1/2" @ 4195' WITH 175 SX

NAME AND 100 S MAIN, SUITE 520 SURFACE CASING: SIZE 10 3/4" @ 273' WITH 255 SX

ADDRESS WICHITA, KS 67202

ABANDONED OIL WELL X GAS WELL INPUT WELL INJ WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 08 MONTH: 12 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM MONTE

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

WERE: PERFS AT 3970-4021

SANDED TO 3820' AND 5 SX CEMENT WITH DUMP BAILER. PUMP DOWN 10 3/4" WITH 300# HULLS - 10 SX

GEL - 50 SX CEMENT - 10 SX GEL - 100# HULLS - 125 SX CEMENT. MAXIMUM PRESSURE AT 600#.

SHUT IN AT 300#.

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 12:00 PM DAY: 08 MONTH: 12 YEAR: 1999

ACTUAL PLUGGING REPORT

SANDED TO 3820' AND 5 SX CEMENT WITH DUMP BAILER. PUMP DOWN 10 3/4" WITH 300# HULLS - 10 SX

KANSAS CORPORATION COMMISSION

GEL - 50 SX CEMENT - 10 SX GEL - 100# HULLS - 125 SX CEMENT. MAXIMUM PRESSURE AT 600#.

SHUT IN AT 300#.

INVOICED

DEC 13 1999

DATE 12/21/99

CONSERVATION DIVISION

REMARKS: USED 60/40 POZMIX 6% GEL BY UNITED CEMENTING. RECOVERED 2010' OF 5 1/2" CASING.

WICHITA, KS

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Richard W. Lacey (TECHNICIAN) FORM CP-2/3

Handwritten signature and initials