

1 040815

12-15

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046

Operator: Raymond Oil Company, Inc.

Name: Raymond Oil Company, Inc.

Address: P.O. Box 48788

Wichita, KS 67201

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 3:45 p.m. Day: 15 Month: 12 Year: 1993

Plugging proposal received from David Brady

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

Size: 5 1/2" at 4121' w/175 sx cement, Perfs at 3974-3994'

1st plug sand back to 3920' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 175 sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 5 p.m. Day: 15 Month: 12 Year: 1993

ACTUAL PLUGGING REPORT 1st plug sanded back to 3920' and dumped 5 sx cement on top of sand bridge through bailer,

2nd plug pumped down 10 3/4" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 10 3/4" wiper plug and pumped 175 sx cement.

Maximum pressure 600 psi and shut in 200 psi.

RECEIVED  
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by United Cementing & Acid Co. Recovered 2610' of casing  
(If additional description is necessary, use BACK of this form.)

**INVOICED**  
Please observe this plugging.

DATE 12-30-93

INV. NO. 39607

Signed Stephen J. Pfeifer  
(TECHNICIAN)  
CONSERVATION DIVISION  
Wichita, Kansas