

To: 1041172
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-185-22,927-0000
SE SW NW, SEC. 33, T. 25 S, R. 11 W 1/2
2970 feet from S section line
4290 feet from E section line

5-16

TECHNICIAN'S PLUGGING REPORT
Operator License # 5046

Lease Name Helmer Well # 1

Operator: Raymond Oil Company, Inc.
Name & Address P.O. Box 48788
Wichita, KS 67201

County Stafford
Well Total Depth 4150 134.87 feet

Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/4 feet 257

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529
Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 9:30 a.m. Day: 16 Month: 5 Year: 19 96

Plugging proposal received from Darrell Kelso

(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

Work: 5 1/2" at 4144' w/175 sx cement, Perfs at 3960-87'

1st plug sand back to 3910' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 4 sx hulls, 10 sx gel, 60 sx cement, 12 sx gel, 1 sx hulls, released 10 3/4"
wiper plug and pump 150 sx cement.

5-23-96

RECEIVED
KANSAS CORP. CO.
MAY 23 11:11 AM '96

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:45 a.m. Day: 16 Month: 5 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 3910' and dumped 5 sx cement on top of sand
bridge through bailer,

2nd plug pumped down 10 3/4" surface pipe with 400 lbs. hulls, 10 sx gel, 60 sx cement, 12
sx gel, 100 lbs. hulls, released 10 3/4" wiper plug and pumped 150 sx cement.

Maximum pressure 800 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by United Cementing & Acid Co. Recovered 2500' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED
DATE JUN 05 1996
INV. NO. 45726

Signed Stephen J. Durrant
(TECHNICIAN)